


CERTIFIED RECORD OF LAND CORNER MONUMENTATION


History of original corner establishment:



Description of corner evidence found:

Description of monument and accessories established to perpetuate the original location of this corner:

Set 2 1/2" x 30" aluminum pipe with 3/4" aluminum cap 26" in ground, marked:



Bearing tree:

28" ponderosa pine - S50°E - 183.4 ft. scribed "S1/16 S6" in upper blaze and "BT" and brass tag stamped RLS 1664 in lower blaze.

Accessory:

3' x 2 1/2' mound of stone - N59°W - 7.8 ft.

Compass declination 19 3/4° East

Note:

I set steel fence post 6' north of corner with 54-9 sign, placed USFS bearing tree and 54-9 sign on bearing tree and in mound of stone, painted red band at breast height on smoothed bark on bearing tree.

I hereby certify the above corner was perpetuated as herein described in June 1983

Witness: Ron Horton

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Carl E. Sundet*  
OREGON  
JULY 14, 1978  
CARL E. SUNDET  
1664

Office of..... County of.....  
State of..... I hereby certify that the within instrument was filed in this office  
for record on the..... day of....., 19.....  
..... by .....  
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

☆ GPO - 798-276

FILED July 25 1983  
BAKER COUNTY SURVEYOR  
SURVEY NO. 8-43-41  
8-44-59