


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established by Barin and Walden under GLO contract no. 198, dated July 15, 1873.

Surveyor's General records state:

Set basalt stone 12 x 8 x 6 ins, 8 ins in the ground for 1/4 sec. cor.




Description of corner evidence found:

At a point which bears N 32° E, 10.3 feet dist from the proportioned 1/4 sec. cor. location found a mound of stone with a stone of proper dimentions but no identified markings.

Description of monument and accessories established to perpetuate the original location of this corner:

Set a 2 1/2 inch brass cap on a 1 inch iron pipe, 31 inches long and projecting 5 inches out of the ground with a surrounding rock mound.

Brass cap marked thus:



I hereby certify that the above described corner monument was correctly re-established on Sept. 24, 1980, under my direct supervision and witnessed by Bill Hanley and Jim DeMastus.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

James D. Hanley
OREGON
SEPTEMBER 23, 1977
JAMES D. HANLEY
1206

Office of..... County of.....
State of..... I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....
..... by
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-5/ (9/71)

FILED Oct. 16, 1980
BAKER COUNTY SURVEYOR
SURVEY NO. 8-44-6