


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

1159

History of original corner establishment:

The original corner was established by W.B. Barr under Contract NO. 388 dated May 7th. 1881. Marked basalt rock 12 X 8 X 6 in.s for 1/4 sec. corner. Raised mound of rock as per instructions.



In May and June 1976 James D. Hanley did a survey in the area. At the intersection of fences he accepted evidence and placed a 2" brass cap.

Description of corner evidence found:

At the corner location I found the fence intersection and the brass cap set by James D. Hanley. There were no accessories set.

Monument stamped:

T8S R44E
S9
1/4 ——— |
S16
CS 1976

Description of monument and accessories I established to perpetuate the original location of this corner:

I set 2 bearing trees from the existing brass cap.

A 26" Ponderosa Pine bears N65°45'E 105.56 ft. marked 1/4S9 BT Nail in W base.

A 24" Ponderosa Pine bears S42°45'E 145.47 ft. marked 1/4S16 BT Nail in E base.

Bearings taken with a staff compass declination 18 1/2° East per 1980 Isogonic chart. Distances pulled to 60d nails with brass washers stamped L.S. 1898 driven in the side center of bearing trees.

17-June 1982

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

Harry C. Hildebrand

OREGON
JULY 12, 1980
HARRY C. HILDEBRAND
1898

Office of..... County of.....
State of..... I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....
..... by

(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

FILED June 22, 1982
BAKER COUNTY SURVEYOR
SURVEY NO. 8-44-14

☆ GPO—798-276

J-11