


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

The original survey was done by Chet M. Foster
Dep. Surveyor in June 1872.

Cor. 4 is a post marked W.H.P. 4



Description of corner evidence found:

At the corner I found a 4"X6"X32" wooden post marked
COR NO 4 lying on the ground beside a 5/8 X 30" plastic
capped rebar set by William Hanley under survey No. 8-44-10.

Description of monument and accessories I established to perpetuate the
original location of this corner:

I replace William Hanley's rebar with a 2 1/2"X32"
brass capped steel pipe 28" in the ground from which

An 8" White Fir bears N 23 E 24.63 ft.
Marked COR 4/MS 11 BT nail in S.E. base.

A 12" White Fir bears S 85 E 18.49 ft.
Marked COR 4/ MS 11 BT nail in N base.

MONUMENT STAMPED
S.G.P. MS.11
COR. 4
1982
OR.L.S.1898

Bearings taken with a staff compass declination
18 1/2 East per 1980 isogonic chart.
Distances pulled to 60d nails with brass washers
stamped L S 1898 driven in the side center of the
bearing trees.

17-June 1982

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**
Harry C. Hildebrand
**OREGON
JULY 18, 1980
HARRY C. HILDEBRAND
1898**

Office of..... County of.....
State of..... I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....
..... by
(COUNTY OFFICIAL) (DEPUTY)