


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

The original survey was done by Chet M. Foster  
Dep. Surveyor, in June 1872.  
Cor 7 is a post marked W H P 7



Description of corner evidence found:

At the corner I found a 4" X 6" X 32" wooden post  
marked C O R N O 7 lying on the ground beside a  
5/8" X 30" plastic capped rebar set for the corner  
by William Hanley under survey NO 8-44-10.

Description of monument and accessories I established to perpetuate the  
original location of this corner:

I replaced William Hanley's rebar with a 2½" x 32"  
brass capped steel pipe 28" in the ground in a mound  
of stone from which

A 7" Ponderosa Pine bears S65°E 26.31 ft.  
marked C O R 7 / MS 11 BT Nail in N. base.

Monument stamped  
S.G.P. MS. 11

A 5" Ponderosa Pine bears S48°W 13.84 ft.  
marked C O R 7 / MS 11 BT



Bearings taken with a staff compass declination 18½° East  
per 1980 Isogonic chart.

1982  
O.R.L.S. 1898

Distances are pulled to 60d nails with brass washers  
stamped L.S.1898 driven in the side center of the  
bearing trees.

*17-June 1982*

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Harry C. Hildebrand*

OREGON  
JULY 13, 1980  
HARRY C. HILDEBRAND  
1898

Office of..... County of... Baker.....  
State of... Oregon..... I hereby certify that the within instrument was filed in this office  
for record on the..... day of....., 19.....  
..... by .....

(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

FILED June 22, 1982  
BAKER COUNTY SURVEYOR  
SURVEY NO. 8-44-19