


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner originally established by W. Barr under contract #388, dated May 17, 1881
Set 12" x 10" x 5" marked lava rock. Raised large mound of rocks.




Description of corner evidence found:

Found 14"x10"x8" stone marked " $\frac{1}{4}$ " in fence jack. This is probably the stone set by Hoffman in 1914 where he found an unmarked stone in a mound. Stone marked " $\frac{1}{4}$ " accepted as best evidence of original corner location.

Description of monument and accessories established to perpetuate the original location of this corner:

Set 2½" x 30" aluminum pipe with ¾" aluminum cap 25" in ground in small mound of stone, marked; Buried marked stone alongside pipe. Placed broken green glass and a crushed aluminum cap in base of hole as memorials, No stones available for mound, pits impracticable



Note:

Set steel fence post with 54-4 sign N75°E - 4.8 ft.

I hereby certify the above corner location was perpetuated as herein described in September 1982.

Frank Vaughn Frank Vaughn, Witness

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Carl E. Sundet
OREGON
JULY 14, 1978
CARL E. SUNDET
1664

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....
..... by

(COUNTY OFFICIAL)

(DEPUTY)