


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner originally established by N. Walden under contract #198, dated July 15, 1873.  
Set basalt rock 18"x10"x8" 8" in ground.



Description of corner evidence found:

Found 15"x9"x7" stone with 1/4 on west face in mound of stone.

Description of monument and accessories established to perpetuate the original location of this corner:

Set 2 1/2" x 30" aluminum pipe with 3/4" aluminum cap, 26" in ground in mound of stone, marked:  
Buried original stone alongside pipe.



Bearing tree:

45" Douglas fir - S01°W - 79.6' - scribed "1/4 S1 BT" in upper blaze and brass tag stamped RLS 1664 in lower blaze

Accessories:

4' x 1' rock mound - N81°E - 17.3' - placed 54-3 and 54-4 sign in rock mound.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Carl E. Sundet*

OREGON  
JULY 14, 1978  
CARL E. SUNDET  
1664

Note:

I set steel fence post 5' North of corner location with USFS attention sign, placed USFS bearing tree signs on bearing tree and painted red band on smoothed bark on bearing tree.

I hereby certify the above corner location was perpetuated as herein described in September 1982.

*Frank Vaughn* Frank Vaughn, Witness

Office of..... County of.....

State of....., I hereby certify that the within instrument was filed in this office

for record on the..... day of....., 19.....

..... by .....

(COUNTY OFFICIAL)

(DEPUTY)

Form R6-7100-57 (9/71)

FILED Oct 19 1982  
BAKER COUNTY SURVEYOR  
SURVEY NO. 8-43-26  
8-44-28

U.S. GPO—796-276