

SUNDET & ASSOCIATES

LAND SURVEYING

LAKEVIEW, OREGON 97630

PHONE 947-3293

P.O. Box 1228

August 14, 1983

SURVEY NARRATIVE TO COMPLY WITH PARAGRAPH 209.250 OREGON REVISED STATUTES

Survey for: Wallowa-Whitman National Forest
P.O. Box 907
Baker, Oregon 97814

Location: Located in Sections 1, 2, 3, 12 & 13,
T.8S. R. 44E., Baker County, Oregon

Purpose: To establish a portion of the North and East
Boundaries of T.8S.R.44E., W.M.

Date: Survey completed in July 1983

Procedure: A traverse was run easterly from the northeast corner
of section 4 to the northeast corner of section 1,
thence southerly to the southeast corner of section
13.

Search positions were computed from all applicable
evidence and checked against record calls.

The original stones were found at the north $\frac{1}{4}$ corner
section 1 and the southeast section corner to section
12. Both of these corners fit calls to nearby drain-
ages as described in the original survey notes.

The east and west $\frac{1}{4}$ corners section 2 were tied in.
The resulting distances and bearings leave no doubt
that the interior lines were not connected to the
north township boundary.

The section corner to sections 1, 2, 35 & 36 falls
in a recent burn and may have been destroyed therein.

The remaining corners fall on steep, unstable hill
sides and the original stones may have slid down during
the intervening years.

All original corners not found this survey were set by
single proportionate measurement.

Bearings are based on solar observation.

Instruments used were a Jena one-second theodolite
and a Mac I-H Electronic Distance Measuring Device.

FILED Aug 22, 1983

BAKER COUNTY SURVEYOR

SURVEY NO. 8-44-65

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Carl E. Sundet

OREGON
JULY 14, 1978
CARL E. SUNDET
1064