


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner was established by W. B. Barr, under GLO Contract No. 388, dated May 7, 1881.

Surveyor General's office records state:

Marked 18 x 14 x 8 stone for 1/4 sec. cor. from which:
 A pine, 18 ins. diam. bears S. 53° W., 28 lks.
 A pine, 18 ins. diam. bears N. 48° E., 20 lks.




Description of corner evidence found:

Found a 18 x 12 x 7 in. stone, mkd. 1/4, with a 5/8 in. rebar with plastic cap mkd. LS 645 alongside.

Description of monument and accessories established to perpetuate the original location of this corner

Set a 2½ in. brass cap on a 2 in. galvanized iron pipe, 30 ins. long, 24 ins. in the ground at the found rebar position. Buried the stone and rebar 1 ft. North.

The monument is marked thus:



I certify the above monument was properly reestablished under my supervision on May 17, 1984, and witnessed by Brad Gordon, Tom Fisk and Jim DeMastus.

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

James D. Hanley
OREGON
 SEPTEMBER 23, 1977
 JAMES D. HANLEY
 1206

Office of Co. Surveyor County of Baker
 State of Ore, I hereby certify that the within instrument was filed in this office
 for record on the May day of 23, 1984
James D. Hanley by _____ (DEPUTY)
 (COUNTY OFFICIAL)

FILED S-23-84
 BAKER COUNTY SURVEYOR
 SURVEY NO. 8-44-66