


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner was established by W. B. Barr, under GLO Contract No. 388, dated May 7, 1881.
 GLO record states:
 "Marked a basalt stone 18 x 10 x 5 for cor. to Secs. 7, 8, 17 and 18. Raised mound of rock as per instructions."



Description of corner evidence found:

Found a 22 x 8 x 6 in. stone on top of a fence rock jack at an ancient fence intersection. Fence runs North and East, remains of fence running South. The stone is now broken in half. A survey was made along the North section lines extending 1/2 mile West, 1/2 mile North and one mile East of the corner position on June 21, 1983 to verify the corner location from the topographic calls in W. Barr field notes of original survey.

A retracement of lines in this section was made by John G. Collins, U. S. Cadastral Engineer, in April, 1924, under special instructions of the Surveyor General. He found a marked stone 18 x 10 x 5, set in mound of stone "standing at the intersection of fences from N., E., S., and W." I feel certain this is the same stone described above, set by W. Barr and later placed atop the fence rock jack.


Description of monument and accessories established to perpetuate the original location of this corner

Set a 2 1/2 in. brass cap on a 2 in. galvanized iron pipe, 30 ins. long, 24 ins. in the ground with raised mound of rock at the fence corner. Buried the found stone 1 ft. South.

Set 4 5/8 in. x 30 in. rebars with plastic caps 10 ft. N., 10 ft. S., 10 ft. E. and 10 ft. W. for references.

I certify the above monument and references were properly reestablished under my supervision on May 17, 1984, and witnessed by Brad Gordon, Tom Fisk and Jim DeMastus.

Monument is marked thus:



**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

James D. Hanley
OREGON
 SEPTEMBER 23, 1977
 JAMES D. HANLEY
 1206

Office of Co. Surveyor County of Baker
 State of Ore, I hereby certify that the within instrument was filed in this office
 for record on the 23 day of May, 1984.
James D. Hanley by _____
 (COUNTY OFFICIAL) (DEPUTY)

FILED 5-23-84
 BAKER COUNTY SURVEYOR
 SURVEY NO. 8-44-67