

RECORD OF SURVEY

SECTION 8, T.8S., R.44E., W.M.

BAKER COUNTY, OREGON

"SPARTA CADASTRAL SURVEY"

(A) SECTION CORNER COMMON TO SECTIONS 4, 5, 8 & 9.
 T8S R44E
 S5 S4
 S8 S9
 1974
 FOUND : 2" I.P. & B/C and following BT's :
 43" P.P. S 09° 49' W, 71.5 ft.;
 26" P.P. N 76° 46' E, 75.9 ft.;
 8" P.P. S 04° 47' E, 12.6 ft.;
 13" P.P. N 44° 55' W, 23.6 ft. Dead;
 11" P.P. N 33° 10' W, 50.1 ft. Dead;

(B) SECTION CORNER COMMON TO SECTIONS 5, 6, 7 & 8.
 T8S R44E
 S6 S5
 S7 S8
 1974
 FOUND : 2" I.P. & B/C in M.O.S. and following BT's :
 17" P.P., S 26° E, 9.9 feet ;
 22 " P.P., S 66° W, 21.7 feet;
 28" P.P., N 16° W, 41.6 feet;
 6" P.P., N 89° E, 10.3 feet;
 6" P.P., N 55° W, 6.9 feet.

(C) SECTION CORNER COMMON TO SECTIONS 8, 9, 16 & 17.
 T8S R44E
 S8 S9
 S17 S16
 1974
 FOUND : 2" I.P. & B/C in M.O.S. AND following BT's.
 19" P.P., N 62° 29' E, 67.0 feet;
 15" P.P., S 66° 52' E, 38.7 feet;
 19" P.P., S 00° 08' W, 75.7 feet;
 19" P.P., N 43° 57' W, 34.7 feet;
 19" Pine stump, S 81° 59' W, 18.1 feet.

(D) SECTION CORNER COMMON TO SECTIONS 7, 8, 17 & 18.
 T8S R44E
 S7 S8
 S18 S17
 CS 1984
 FOUND : 2" I.P. & B/C 5" high in M.O.S and following
 5/8" I.R., N 00° 11' E, 10.00 feet ;
 5/8" I.R., S 89° 54' E, 10.00 feet;
 5/8" I.R., S 00° 12' W, 10.00 feet;
 5/8" I.R., N 89° 54' W, 10.00 feet.

(E) 1/4 CORNER COMMON TO SECTIONS 5 & 8.
 T8S R44E
 1/4 S5
 S8
 1982
 FOUND : 2" A.P. 6" high in M.O.S. and following BT's :
 10" P.P., S 28° 43' W, 93.0 feet;
 6" P.P., N 67° 37' E, 33.4 feet;
 36" Pine stump, S 75° 46' W, 20.4 feet.

(F) 1/4 CORNER COMMON TO SECTIONS 7 & 8.
 T8S R44E
 1/4 S7
 S8
 1985
 FOUND : fence corner as best evidence, and possible stone.
 SET : A.P. in M.O.S. and following :
 5/8"x30" I.R. with A.C. N 06° E, 13.47 feet, mkd. "RM 13.47";
 5/8"x30" I.R. with A.C. S 88° 15' W, 13.22 feet, mkd. "RM 13.22".

(G) 1/4 CORNER COMMON TO SECTIONS 8 & 9.
 T8S R44E
 1/4 S8
 S9
 1985
 FOUND : Fence corner as best evidence.
 SET : A.P. in M.O.S. and following:
 6" P.P., N 16° 15' W, 81.2 feet, mkd. "1/4 S 8 BT";
 20" P.P., N 41° E, 71.8 feet, mkd. "1/4 S 9 BT"
 VAR. USED = 17-1/2° E

(H) SOUTH 1/16 CORNER COMMON TO SECTIONS 8 & 9.
 T8S R44E
 S 1/16
 S8 S9
 1985
 SET : 2" A.P. and the following :
 10" P.P., N 74° 30' W, 29.7 feet, mkd., " S 1/16 S 8 BT".
 6" P.P., S 18° 36' E, 26.3 feet, mkd., " S 1/16 S 9 BT".

(I) CENTER 1/4 CORNER SECTION 8.
 T8S R44E
 C 1/4
 S8
 1985
 SET : 2" A.P. and the following :
 7" P.P., N 61° 56' W, 58.4 feet, mkd., " C 1/4 S 8 BT".
 7" P.P., N 13° 51' E, 204.2 feet, mkd., " C 1/4 S 8 BT".

(J) NORTH 1/16 CORNER COMMON TO SECTION 7 & 8.
 T8S R44E
 N 1/16
 S7 S8
 1985
 FOUND : mkd. stone, 19"x14"x8" lying loose 4 feet Southwest.
 SET : 2" A.P. in M.O.S. and the following ;
 30" P.P., N 06° 01' W, 209.5 feet, mkd., " N 1/16 S 7 BT".
 6" P.P., N 17° 27' E, 323.2 feet, mkd., " N 1/16 S 8 BT".

(K) SOUTHEAST 1/16 CORNER SECTION 8.
 T8S R44E
 SE 1/16
 S8
 1985
 SET : 12" A.P. and the following :
 5/8"x30" I.R., S 86° 17' W, 9.1 feet, mkd., " RM, 9.1";
 5/8"x30" I.R., S 02° 39' E, 9.8 feet, mkd., " RM, 9.8".

(L) 1/4 CORNER COMMON TO SECTIONS 8 & 17.
 T8S R44E
 S8
 1/4 S17
 1985
 FOUND : Fence corner as best evidence & stone with possible marks,
 14"x7"x5" lying near by.
 SET : 2" A.P. in M.O.S. and the following :
 5/8"x30" I.R. with A.C., N 86° 07' W, 9.98 feet, mkd., "RM 9.98".
 5/8"x30" I.R. with A.C., S 13° 25' E, 11.20 feet, mkd., "RM 11.20".

(M) CENTER NORTH 1/16 CORNER SECTION 8.
 T8S R44E
 N 1/16 S8
 C
 1985
 FOUND : mkd. stone, 8"x12"x18" in collar of stone, by Hoffman.
 SET : 2" A.P. and the following;
 10" P.P., N 42° 48' E, 118.4 feet, mkd., " CN 1/16 S 8 BT".
 14" P.P., N 88° 20' E, 30.0 feet, mkd., " CN 1/16 S 8 BT".
 HOFFMANS POSITION WAS S 88° 32' W, 25.6 FT. FROM TRUE.
 PLACED HIS STONE & MOUND AROUND THE ABOVE A.P.

(N) CENTER EAST 1/16 CORNER SECTION 8.
 T8S R44E
 E 1/16
 C C
 S8
 1985
 SET : 2" A.P. in M.O.S. and the following :
 5/8"x30" I.R. with A.C., N 00° 02' E, 10.76 feet, mkd., "RM 10.8";
 5/8"x30" I.R. with A.C., N 89° 56' E, 9.0 feet, mkd., " RM 9.0".

(P) NORTHEAST 1/16 CORNER SECTION 8.
 T8S R44E
 NE 1/16
 S8
 1985
 FOUND : mkd. stone, 16X10"x6" by Hoffman, lying loose and disturbed by
 dozing, approximately 50 feet South of true position.
 SET : 2" A.P. in M.O.S. and the following;
 24" P.P., N 66° 43' E, 150.4 feet, mkd., " NE 1/16 S 8 BT";
 19" P.P., S 60° 41' E, 153.0 feet, mkd., " NE 1/16 S 8 BT".

NOTE: SEE CORNER RESTORATIONS I FILED (FORM R6-7100-57)
 WITH THE BAKER CO. SURVEYOR FOR MORE
 COMPLETE DATA.

FILED June 16, 1986
 BAKER COUNTY SURVEYOR
 SURVEY NO. 8-44-18

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR
 Ronald H. Schulson
 OREGON
 RONALD H. SCHULSON
 1985

SURVEY PREPARED FOR AND AT THE REQUEST OF U.S. FOREST SERVICE		NO. S-8611 SCALE: N/A DATE: 4-30-86
LOCATION OR DESCRIPTION: CONTRACT No. 53-04H1-4-9624N ALL OF SECTION 8 T 8 S R 44 E W M BAKER COUNTY, OREGON		FIELD BOOK No. 1-5 INDICATES RECORD DISTANCE AND BEARING
J. & R. SURVEYORS P.O. BOX 418 DALLAS, OREGON 97338 TELEPHONE: 623-4003		