

MAP OF SURVEY SECTION 10, T.8S., R. 44E., W.M. BAKER COUNTY, OREGON

"SPARTA CADASTRAL SURVEY"

T8S R44E
S4 | S3
S9 | S10
1974

A SECTION CORNER COMMON TO SECTIONS 3, 4, 9 & 10.

FOUND: 2" I.P. with BLM B/C.
23" P.P., N33°31'W, 120.8 ft.
36" P.P., Decayed Stump, N21°10'E, 49.5 ft.
19" P.P., N21°11'E, 24.7 ft.
15" P.P., S77°40'E, 31.7 ft.
14" P.P., S29°24'W, 31.5 ft.
12" P.P., N42°27'W, 51.5 ft.

T8S R44E
N 1/16
S10 | S11
1985
LS 1658

E NORTH 1/16 CORNER COMMON TO SECTIONS 10 & 11.

SET: 2" A.P. in small M.O.S.
9" P.P., S26°48'W, 76.3 ft.
16" P.P., S58°30'E, 106.1 ft.

T8S R44E
1/4
S10 | S11
1974

I 1/4 CORNER COMMON TO SECTIONS 10 & 11.

FOUND: 2" I.P. with BLM B/C, in M.O.S.
24" P.P., N22°48'E, 61.4 ft.
18" P.P., double broken stub, N04°06'W, 107.3 ft.
15" P.P., N06°37'W, 170.6 ft.

T8S R44E
S3
1/4
S10
1982
LS 1658

B 1/4 CORNER COMMON TO SECTIONS 3 & 10.

FOUND: 2" A.P. in small M.O.S.
24" Rotten Pine Stump, N26°W, 62.0 ft. to face.
11" P.P., N33°30'E, 22.6 ft.
10" P.P., S74°30'E, 34.5 ft.

T8S R44E
1/4
S9 | S10
1985
LS 1658

F 1/4 CORNER COMMON TO SECTIONS 9 & 10.

FOUND: An unrecorded iron rod, stone and evidence of the original BT's.
SET: 2" A.P. 28" in the ground at the record distance from the BT's and buried the unrecorded marked stone on the West side of the A.P. from which bear:
(40" Pine, N58°E, 64.7 feet.) Now stump hole; N58°53'E, 64.7 ft.
(40" Pine, N17°W, 29.7 feet.) Now 36" stump with outer wood where scribe would have been rotted away.
N6°33'W, 29.7 feet to estimated face.
10" P.P., S60°W, 14.8 feet, mkd., "1/4 S9 BT";
18" P.P., S50°45'E, 36.0 feet, mkd., "1/4 S10 BT".
The found 5/8" iron rod bears N42°44'E, 1.39 feet.

T8S R44E
S9 | S10
S16 | S15
1985
LS 1658

J SECTION CORNER COMMON TO SECTIONS 9, 10, 15 & 16.

FOUND: A four way fence corner but no trace of stone or stone mound. Since Collins in 1924 called for a stone and stone mound at a four way fence corner and since his topography and calls fit well, I held the alignment of the four fences as the best evidence of this corner.
SET: 2" A.P. in M.O.S. and the following:
5/8"x30" iron rod with A.C., N50°04'E, 15.35 feet, mkd."RM 15.35".
5/8"x30" iron rod with A.C., S00°44'E, 62.24 feet, mkd."RM 62.24".
5/8"x30" iron rod with A.C., S87°40'W, 12.41 feet, mkd."RM 12.41".
5/8"x30" iron rod with A.C., N12°08'W, 18.06 feet, mkd."RM 18.06".

T8S R44E
S3 | S2
S10 | S11
1974

C SECTION CORNER COMMON TO SECTIONS 2, 3, 10 & 11.

FOUND: 2" I.P. with B/C.
27" D.F., S59°04'E, 43.6 ft.
14" TAM., N40°11'E, 47.9 ft.
Rotted Fir Stump, N23°30'E, 4.7 ft.
11" P.P., N17°23'W, 66.6 ft.
15" Fir, Uprooted, N81°W, 22.0 ft.
22" Stump, S87°40'W, 42.0 ft.
14" D.F., S64°W, 89.5 ft.

T8S R44E
C 1/4
S10
1985
LS 1658

G CENTER 1/4 CORNER SECTION 10.

SET: 2" A.P. with 2 stones beside.
10" P.P., N07°E, 41.6 ft.
9" P.P., S70°18'E, 9.4 ft.

T8S R44E
1/4
S10
S15
1985
LS 1658

K 1/4 CORNER COMMON TO SECTIONS 10 & 15.

FOUND: NO trace of original stone or mound, Thus, re-established this corner by proportion.
I found a 5/8" I.R. with plastic cap mkd. "LS 645", N88°57'E, 4.2 ft. from proportion position.
SET: 2" A.P. in M.O.S.
14" P.P., N06°19'E, 81.5 ft.
18" P.P., S82°14'E, 44.4 ft.

T8S R44E
NE 1/16
S10
1985
LS 1658

D NORTHEAST 1/16 CORNER SECTION 10.

SET: 2" A.P. in collar of stone.
9" P.P., N88°23'W, 28.9 ft.
8" P.P., S08°E, 22.4 ft.

T8S R44E
E 1/16
C - C
S10
1985
LS 1658

H CENTER EAST 1/16 CORNER SECTION 10.

SET: 2" A.P. in M.O.S.
27" P.P., N42°53'W, 128.3 ft.
27" P.P., N21°08'W, 180.2 ft.

T8S R44E
S10 | S11
S15 | S14
1986
LS 1658

L SECTION CORNER COMMON TO SECTIONS 10, 11, 14 & 15.

FOUND: NO trace of original post or mound, Thus, re-established this corner by double proportion.
SET: 2" A.P. in M.O.S.
17" P.P., N60°57'W, 506.3 ft. No suitable trees closer in NW quadrant and no trees at all in NE, SE or SW quadrants, Thus, set RM's. where they might get some protection from fence lines.
5/8" I.R., S89°35'W, 10.00 ft.
5/8" I.R., S00°25'E, 10.00 ft.

T8S R44E
S9 | S10
S16 | S15
1985
LS 1658

M SECTION CORNER COMMON TO SECTIONS 9, 10, 15 & 16.

FOUND: A four way fence corner but no trace of stone or stone mound. Since Collins in 1924 called for a stone and stone mound at a four way fence corner and since his topography and calls fit well, I held the alignment of the four fence as the best evidence of this corner.
SET: 2" A.P. in M.O.S. and the following:
5/8"x30" iron rod with A.C., N50°04'E, 15.35 feet, mkd."RM 15.35".
5/8"x30" iron rod with A.C., S00°44'E, 62.24 feet, mkd."RM 62.24".
5/8"x30" iron rod with A.C., S87°40'W, 12.41 feet, mkd."RM 12.41".
5/8"x30" iron rod with A.C., N12°08'W, 18.06 feet, mkd."RM 18.06".

T8S R44E
1/4
S16 | S15
CS 1976

N 1/4 CORNER COMMON TO SECTIONS 15 & 16.

FOUND: 1" I.P. & B/C with 1 foot diameter gear around I.P.
SET: 7" D.F., N79°15'E, 21.4 feet, mkd., "1/4 S15 BT";
22" D.F., N78°30'W, 70.4 feet, mkd., "1/4 S16 BT".

T8S R44E
1/4
S15 | S14
CS 1984

O 1/4 CORNER COMMON TO SECTION 14 & 15.

FOUND: 2" I.P. & B.C. in M.O.S. no positive evidence of BT's.
SET: 13" D. Fir, N20°E, 49.3 feet, mkd., "1/4 S14 BT";
8" P.P., S69°W, 9.1 feet, mkd., "1/4 S15 BT".

NOTE: SEE CORNER RESTORATIONS I HAVE FILED (FORM R6-7100-57) WITH THE BAKER CO. SURVEYOR FOR MORE COMPLETE DATA.

FILED 7-16-86
BAKER COUNTY SURVEYOR
SURVEY NO. 8-44-108

REGISTERED
PROFESSIONAL
LAND SURVEYOR
Ronald H. Schulson
OREGON
JULY 14 1979
RONALD H. SCHULSON
1658

RECORD OF SURVEY PREPARED FOR AND AT THE REQUEST OF WALLOWA-WHITMAN NATIONAL FOREST	J & R No: S-8609
J & R SURVEYORS P.O. BOX 418, DALLAS, OR. 97338	SCALE: N/A
TELEPHONE: (503) 623-4003	DATE: MAY 30, 1986
TAX LOT OR D.L.C.	FIELD BOOK NO. 1-5
All 1/4 sec. 10 T. 8 S. R. 44 E. W.M. BAKER COUNTY	CONTRACT NO. 53-04H1-4-9624N