

**MAP OF SURVEY
SECTION 1, T.8S., R. 44E., W.M.
BAKER COUNTY, OREGON**
"SPARTA CADASTRAL SURVEY"

A SECTION CORNER COMMON TO SECTIONS 1 & 2 of T8S & 35 & 36 of T7S.

FOUND: 2" A.P.
13" P.P., (N44-1/2°W, 51.0 ft.) dead.
16" P.P., (N43-1/2°E, 64.1 ft.)
10" P.P., (S34°E, 85.1 ft.) dead.
9" P.P., (S70-1/2°W, 71.0 ft.)

T7S R44E
S35 | S36
S2 | S1
T8S
1983
LS 1658

T8S
R44E R45E
1/4
S1 | S6
1983
LS 1658

E 1/4 CORNER COMMON TO SECTIONS 1, R44E & 6, R45E.

FOUND: 2" A.P. in M.O.S.
22" P.P., S74°18'W, 120.0 ft.
34" P.P., N72°E, 206.2 ft.

T8S R44E
W 1/16 S1
S12
1986
LS 1658

I WEST 1/16 CORNER COMMON TO SECTIONS 1 & 12.

SET: 2" A.P. in M.O.S.
5/8"x30" I.R., S88°17'W, 10.00 ft.
5/8"x30" I.R., S00°40'E, 10.00 ft.

B 1/4 CORNER COMMON TO SECTIONS 1, T8S & 36, T7S.

FOUND: 2" A.P. in M.O.S.
5" P.P., N65°23'E, 13.5 ft.
12" P.P., S25°32'E, 27.4 ft.

T7S R44E
S36
1/4 S1
T8S
1982
LS 1658

T8S R44E
S 1/16
S2 | S1
1985
LS 1658

F SOUTH 1/16 CORNER COMMON TO SECTIONS 1 & 2.

SET: 2" A.P. in M.O.S.
10" P.P., N70°44'E, 43.0 ft.
14" D.F., S01°11'W, 34.1 ft.

T8S R44E
E-W S1
1/64 S12
1986
LS 1658

J E-W 1/64 CORNER COMMON TO SECTIONS 1 & 12.

SET: 2" A.P. in M.O.S.
5/8"x30" I.R., N02°20'E, 82.36 ft.
5/8"x30" I.R., N88°17'E, 50.23 ft.

C 1/4 CORNER COMMON TO SECTIONS 1 & 2.

FOUND: 2" I.P. with BLM B/C in M.O.S.
13" D.F., N54°W, 27.5 ft.
36" D.F., S25°W, 6.4 ft.
30" D.F., snag, S29°E, 28.9 ft.
6" D.F., N56°E, 25.7 ft.

T8S R44E
1/4 S1
1974

T8S R44E
cesw 1/64
S1
1986
LS 1658

G CENTER-EAST SOUTHWEST 1/64 CORNER SECTION 1.

SET: 2" A.P. in M.O.S.
8" D.F., S74°30'E, 31.6 ft.
6" D.F., S00°58'E, 2.8 ft.

T8S R44E
1/4 S1
S12
1986
LS 1658

K 1/4 CORNER COMMON TO SECTIONS 1 & 12.

FOUND: No trace of the original corner thus at the single proportion position:
SET: 2" A.P. in M.O.S.
5/8" x 30" I.R., S01°22'E, 478.1'
"t" on top of BASALT ROCK OUTCROP, 5' x 2.5' x 1.5' high, N38°16'E, 16.7'
"t" on top of BASALT ROCK OUTCROP, 4' x 3' x 10" high, S62°59'E, 22.1'

D CENTER 1/4 CORNER SECTION 1.

SET: 2" A.P. in M.O.S.
11" P.P., N75°59'W, 73.9 ft.
14" P.P., N05°23'W, 105.9 ft.

T8S R44E
C 1/4 S1
1986
LS 1658

T8S R44E
S2 | S1
S11 | S12
1986
LS 1658

H SECTION CORNER COMMON TO SECTIONS 1, 2, 11 & 12.

FOUND: SMALL M.O.S. pointed out by land owner as having been accepted as the corner for many years. Since this M.O.S. fits records very well, I accepted it as the best evidence of this corner.
SET: 2" A.P. in center of said M.O.S. & erected a larger M.O.S. around said A.P. and the following references:
23" P.P., Southerly fork of double tree, N63°49'E, 274.4 ft.
"t" on top ROCK OUTCROP, 5' x 3' x 1' high, S06°29'W, 103.0'
"t" on top ROCK OUTCROP, 10' x 3' x 18" high, S59°42'E, 181.5'
"t" on the SE face ROCK OUTCROP, 50' x 2' - 3' high, N46°42'W, 106.6'

T8S
R44E R45E
S1 | S6
S12 | S7
1983
LS 1658

L SECTION CORNER COMMON TO SECTIONS 1 & 12, R44E & 6 & 7, R45E.

FOUND: 2" A.P. in M.O.S.
10" D.F., N00°33'W, 8.5 ft.
8" D.F., N75°48'E, 17.7 ft.
6" D.F., S47°53'E, 3.0 ft.
7" D.F., S44°15'W, 13.3 ft.

NOTE: SEE CORNER RESTORATIONS I HAVE FILED (FORM R6-7100-57) WITH THE BAKER CO. SURVEYOR FOR MORE COMPLETE DATA.

FILED July 31, 1986
BAKER COUNTY SURVEYOR
SURVEY NO. 8-44-111

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Ronald H. Schulson

OREGON
RONALD H. SCHULSON
1658

RECORD OF SURVEY
PREPARED FOR AND AT THE REQUEST OF
WALLOWA WHITMAN NATIONAL FOREST

J & R SURVEYORS
P.O. BOX 418, DALLAS, OR. 97338
TELEPHONE: (503) 623-4003

TAX LOT OR D.L.C.
ALL 1/4 SEC. 1, T. 8 S., R. 44 E., W.M., BAKER COUNTY

J & R No: 58616

SCALE: N/A

DATE: 6-30-86

FIELD BOOK NO. 1-5

CONTRACT NO
53-04HI-4-9624N