


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Original GLO by W. Barr, in 1881 set lava rock 12"x10"x8" & in mound of rock.




Description of corner evidence found:

NO trace found.

Description of monument and accessories | established to perpetuate the original location of this corner:

At single proportion position I, set 2"x30" Aluminum pipe with 3/4" Aluminum Cap, marked as shown hereon, 10" in the ground & in mound of stone.
 5/8"x30" Iron rod with Aluminum cap, 16" in the ground, South 21.68 feet, marked "RM 21.68' -->".
 5/8"x30" Iron rod with Aluminum cap, 16" in the ground, North 12.89 feet, marked "RM 12.89' -->".
 6' steel post with signs 54-3 & 54-9 beside each RM.
 6' steel post with signs 54-2 & 54-9, 3' West.



Witnessed by: R.J. Schulson
 B. Haynes

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

7-10-86
Ronald H. Schulson

OREGON
 JULY 14, 1978
 RONALD H. SCHULSON
 1658

Office of..... County of Baker
 State of..... I hereby certify that the within instrument was filed in this office
 for record on the..... day of..... 19.....

..... by
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

☆ U.S. GOVERNMENT PRINTING OFFICE - 1983-793-276

FILED July 31, 1986
 BAKER COUNTY SURVEYOR
 SURVEY NO. B-44-127