

# MAP OF SURVEY SECTION 12, T8S., R. 44E., W.M. BAKER COUNTY, OREGON

"SPARTA CADASTRAL SURVEY"

(A) SECTION CORNER COMMON TO SECTIONS 1, 2, 11 & 12.

FOUND: SMALL M.O.S. pointed out by land owner as having been accepted as the corner for many years. Since this M.O.S. fits records very well, I accepted it as the best evidence of this corner.  
SET: 2" A.P. in center of said M.O.S. & erected a larger M.O.S. around said A.P. and the following references:  
23" P.P., Southerly fork of double tree, N63°49'E, 274.4 ft.  
"+" on top of rock outcrop, 5'x3'x1' high, S06°29'W, 103.0 ft.  
"4" on SE face of rock outcrop, 50'x2'x3' high, N46°42'W, 106.6 ft.  
"4" on top of rock outcrop, 10'x3'x18" high, S59°42'E, 181.5 ft.

T8S R44E  
S21 S1  
S11 S12  
1986  
LS 1658

(B) WEST 1/16 CORNER COMMON TO SECTIONS 1 & 12.

SET: 2" A.P. in M.O.S.  
5/8"x30" I.R., S88°17'W, 10.00 ft.  
5/8"x30" I.R., S00°40'E, 10.00 ft.

T8S R44E  
W 1/16 S1  
S12  
1986  
LS 1658

(C) E-W 1/64 CORNER COMMON TO SECTIONS 1 & 12.

SET: 2" A.P. in M.O.S.  
5/8"x30" I.R., N02°20'E, 82.36 ft.  
5/8"x30" I.R., N88°17'E, 50.23 ft.

T8S R44E  
E-W 1/64 S1  
S12  
1986  
LS 1658

(D) 1/4 CORNER COMMON TO SECTIONS 1 & 12.

FOUND: No trace of the original corner thus at the single proportion position I:  
SET: 2" A.P. in M.O.S.  
"4" on top of basalt outcrop rock, 5'x2.5'x1.5' high, N38°16'E, 16.7 feet.  
"4" on top of basalt outcrop rock, 4'x3'x10" high, S62°59'E, 22.1 feet.  
5/8"x30" I.R. S01°22'E, 478.18 feet.

T8S R44E  
1/4 S1  
S12  
1986  
LS 1658

(E) SECTION CORNER COMMON TO SECTIONS 1 & 12, R44E & 6 & 7, R45E.

FOUND: 12" A.P. in M.O.S.  
10" D.F., N00°33'W, 8.5 ft.  
8" D.F., N75°48'E, 17.7 ft.  
6" D.F., S47°53'E, 3.0 ft.  
7" D.F., S44°15'W, 13.3 ft.

T8S R44E R45E  
S1 S16  
S12 S17  
1982  
LS 1658

(F) N-N 1/64 CORNER COMMON TO SECTIONS 11 & 12.

SET: 2" A.P. in M.O.S.  
5/8"x30" I.R., N00°08'E, 13.27 ft.  
5/8"x30" I.R., N88°23'E, 12.17 ft.

T8S R44E  
N-N 1/64 S11  
S12  
1986  
LS 1658

(G) CNNW 1/64 CORNER TO SECTION 12.

SET: 2-3/8"x30" A.P. with 3-1/4" A.C.  
4" in the ground to rock, & erected large mound of stone, to near top of pipe.  
"4" on top of implanted basalt boulder rock, 3'x3'x6" high, N62°08'E, 49.3 ft. with small M.O.S. on E. side with signs 54-9 & 54-3.  
"4" on top of implanted basalt boulder rock, 4'x3'x6" high, S65°55'E, 27.1 ft. with small M.O.S. on E. side with signs 54-9 & 54-3.  
Set 6' steel post 2' S88°23'W, with signs 54-9 & 54-2.  
Set 6' steel post 18' N00°37'W, with sign 54-2.

T8S R44E  
CNNW 1/64 S12  
1986  
LS 1658

(H) CN 1/16 CORNER TO SECTION 12.

SET: 2-3/8"x30" A.P. with 3-1/4" A.C.  
20" in the ground & in a M.O.S.  
13" P.Pine, S03°45'W, 45.8 ft., Mkd., "CN 1/16 S12 BT".  
9" P.Pine, (easterly of double tree), N53°12'W, Mkd., "CN 1/16 S12 BT".  
Each with 6" red painted band & face & brass LS washer and signs 54-9 & 54-2.  
6' steel post 5 feet E & 11 feet N with signs 54-9 & 54-2.

T8S R44E  
CN 1/16 S12  
1986  
LS 1658

(I) CWNE 1/64 CORNER TO SECTION 12.

SET: 2-3/8"x30" A.P. with 3-1/4" A.C.  
16" in the ground & in a M.O.S.  
18" P.Pine, S32°58'W, 183.0 ft., Mkd., "CWNE 1/64 S12 BT".  
5" P.Pine, S86°11'W, 163.0 ft., Mkd., "X BT".  
Each BT has 6" red painted band & face & brass LS washer and signs 54-9 & 54-3.  
6' steel post 10' S & 5' W with signs 54-9 & 54-2.

T8S R44E  
CWNE 1/64 S12  
1986  
LS 1658

(J) 1/4 CORNER COMMON TO SECTIONS 11 & 12.

FOUND: Original Lava Rock, 12"x8"x7" with marks on E. face, in small M.O.S. In place of said rock I,  
SET: 2" A.P. in M.O.S.  
5/8"x30" I.R., N89°32'E, 39.91 ft.  
5/8"x30" I.R., S89°32'W, 40.00 ft.

T8S R44E  
1/4 S11  
S12  
1985  
LS 1658

(K) C 1/4 CORNER TO SECTION 12.

SET: 2-3/8"x30" A.P. with 3-1/4" A.C.  
14" in the ground & in a M.O.S.  
14" P.Pine, N01°14'W, 283.6 ft., Mkd., "C1/4 S12 BT".  
"4" on firmly planted basalt boulder rock, 3'x3'x1.5' high, N48°14'E, 280.1 ft. with signs 54-9 & 54-3.  
BT has 6" red painted band & face & brass LS washer & signs 54-9 & 54-3.  
6' steel post set 0.5 ft. SW with sign 54-9.

T8S R44E  
C 1/4 S12  
1986  
LS 1658

(M) EAST 1/4 CORNER TO SECTION 12.

FOUND: 2" A.P. in M.O.S.  
13" P.P., N50-1/2°W, 109.3 ft.  
17" P.P., N86°E, 137.2 ft.

T8S R44E R45E  
S12 S17  
1982  
LS 1658

(L) ONE 1/64 CORNER TO SECTION 12.

SET: 2-3/8"x30" A.P. with 3-1/4" A.C.  
20" in the ground & in a M.O.S.  
17" P.Pine, S05°17'W, 357.9 ft., Mkd., "CWE 1/64 S12 BT".  
"4" on top of firmly implanted basalt boulder rock, 2.5'x2'x1.5' high, S66°57'E, 19.02 ft., with signs 54-9 & 54-3 beside.  
Set 6' steel post 5 feet N with signs 54-9 & 54-2.  
BT has 6" red painted band & face & brass LS washer and signs 54-9 & 54-3.

T8S R44E  
CWE 1/64 S12  
1986  
LS 1658

(N) CS 1/16 CORNER TO SECTION 12.

SET: 2-3/8"x30" A.P. with 3-1/4" A.C.  
4" in the ground & in a large M.O.S.  
12" P.Pine, S65°35'E, 55.8 ft., Mkd., "CS 1/16 S12 BT".  
9" P.Pine, S17°32'E, 159.3 ft., Mkd., "CS 1/16 S12 BT".  
Each BT has 6" red painted band & face & brass LS washer & signs 54-9 & 54-3.  
Set 6' steel post 45 ft. E. & 5 ft. S. with signs 54-2 & 54-9.

T8S R44E  
CS 1/16 S12  
1986  
LS 1658

(O) CWSE 1/64 CORNER TO SECTION 12.

SET: 2-3/8"x30" A.P. with 3-1/4" A.C.  
18" in the ground and in a M.O.S.  
16" P.Pine, S61°05'W, 115.6 ft., Mkd., "CWSE 1/64 S12 BT".  
9" P.Pine, S24°53'W, 178.0 ft., Mkd., "CWSE 1/64 S12 BT".  
Each BT has 6" red painted band & face & brass LS washer & signs 54-3 & 54-9.  
Set 6' steel post 5 ft. W. & 5 ft. N. with signs 54-9 & 54-2.

T8S R44E  
CWSE 1/64 S12  
1986  
LS 1658

(P) CSSW 1/64 CORNER TO SECTION 12.

SET: 2-3/8"x30" A.P. with 3-1/4" A.C.  
10" in the ground & in M.O.S.  
Set 5/8" I.R. in stone mound, N89°10'E, 125.14 ft., Mkd., "RM 125.14 -->".  
"4" on top of imbedded Basalt rock, 4'x3'x1' high, S00°17'E, 124.75 ft.  
6' steel post with signs 54-9 & 54-3 in mound with the I.R.  
6' steel post with signs 54-9 & 54-2 4' E. of Monument.  
6' Steel post with signs 54-9 & 54-3 & 54-2 in M.O.S. 3' S. of "4" on rock.

T8S R44E  
CSSW 1/64 S12  
1986  
LS 1658

(Q) CSS 1/64 CORNER TO SECTION 12.

SET: 2-3/8"x30" A.P. with 3-1/4" A.C.  
10" in the ground & in M.O.S.  
17" P.Pine, N13°39'E, 207.1 ft., Mkd., "CSS 1/64 S12 BT".  
"4" on Rock outcrop, 1' square smooth surface near top of E. face of 5' high outcrop which runs Approx. 50' N-S. The marked rock is near center of outcropping.  
6' steel post 4' N. & 7' W. with 54-9 & 54-2 signs.  
54-9 & 54-3 signs placed on rock "4" in on.  
BT has 6" red painted band & face & brass LS washer & signs 54-9 & 54-3.

T8S R44E  
CSS 1/64 S12  
1986  
LS 1658

(R) SECTION CORNER COMMON TO SECTIONS 11, 12, 13 & 14.

FOUND: No trace of the original stone or mound thus at the double proportion position I;  
SET: 2" A.P. in M.O.S. and the following RM's;  
M.O.S., S36°31'W, 16.5 ft.  
M.O.S., S66°48'E, 18.0 ft.  
Basalt Rock, 3'x3'x2' high with + on top, N36°31'E, 8.12 ft.  
Basalt Rock, 2.5'x2.5'x 8" high with + on top, N66°48'W, 21.4 ft.

T8S R44E  
S11 S12  
S13 S14  
1986  
LS 1658

(S) W 1/16 CORNER COMMON TO SECTIONS 12 & 13.

SET: 2-3/8"x30" A.P. with 3-1/4" A.C.  
15" in the ground & in M.O.S.  
5/8"x30" I.R. with A.C., N00°55'W, 16.72 ft., Mkd., "RM 16.72 -->".  
5/8"x30" I.R. with A.C., N89°20'E, 21.54 ft., Mkd., "RM 21.54 -->".  
Set 6' steel post with signs 54-2 & 54-3, 6" from each RM.  
Set 6' steel post with sign 54-9, 3 ft. South.

T8S R44E  
W 1/16 S12  
S13  
1986  
LS 1658

(T) 1/4 CORNER COMMON TO SECTIONS 12 & 13.

Orig: By W. Barr, 1881, set LAVA rock, 12"x10"x8" in mound of rock. NO trace found.  
At single proportion position I,  
SET: 2-3/8"x30" A.P. with 3-1/4" A.C.  
10" in the ground & in M.O.S.  
5/8"x30" I.R. with 3-1/4" A.C., 16" in the ground, South 21.68', Mkd., "RM 21.68 -->".  
5/8"x30" I.R. with 3-1/4" A.C., 16" in the ground, North 12.89', Mkd., "RM 12.89 -->".  
6' steel post with signs 54-3 & 54-9 beside each RM.  
6' steel post with signs 54-9 & 54-2, 3' West.

T8S R44E  
1/4 S12  
S13  
1986  
LS 1658

(U) E 1/16 CORNER COMMON TO SECTIONS 12 & 13.

SET: 2-3/8"x30" A.P. with 3-1/4" A.C.  
8" in the ground & in large M.O.S.  
6'x10'x4' high rock outcrop N36°53'W, 114.8 ft., Mkd., "4" BO" on 1 foot square smooth surface on SE face of Rock.  
5/8"x30" I.R. with 3-1/4" A.C. N89°20'E, 41.36 ft., Mkd., "RM 41.36 -->".  
Set 6' steel post with signs 54-2, 54-3 & 54-9, 0.5 ft. from RM.  
Set 6' steel post with signs 54-9 & 54-2 5' West.

T8S R44E  
E 1/16 S12  
S13  
1986  
LS 1658

(V) SOUTH-EAST CORNER TO SECTION 12.

FOUND: 2" A.P. in M.O.S., 24" high & M.O.S. N23°W, 10.9 ft.;  
M.O.S. N62-1/2°E, 7.2 ft.;  
M.O.S. S17°E, 15.4 ft.;  
M.O.S. S55°W, 10.4 ft.  
See Surv. By SUNDET.

T8S R44E R45E  
S12 S17  
S13 S18  
1982  
LS 1658

(W) SECTION CORNER COMMON TO SECTIONS 9, 10, 15, & 16.

FOUND: A four way fence corner but no trace of stone or stone mound. Since Collins in 1924 called for a stone and stone mound at a four way fence corner and since his topography and calls fit well, I held the alignment of the four fences as the best evidence of this corner.  
SET: 2" A.P. in M.O.S. and the following:  
5/8"x30" iron rod with A.C., N50°04'E, 15.35 feet, mkd."RM 15.35".  
5/8"x30" iron rod with A.C., S00°44'E, 62.24 feet, mkd."RM 62.24".  
5/8"x30" iron rod with A.C., S87°40'W, 12.41 feet, mkd."RM 12.41".  
5/8"x30" iron rod with A.C., N12°08'W, 18.06 feet, mkd."RM 18.06".

T8S R44E  
S9 S10  
S16 S15  
1985  
LS 1658

(X) SECTION CORNER COMMON TO SECTIONS 25, 26, 35, & 36.

FOUND: Original Lava Rock, 27"x16"x14" w/notches.  
SET: 2" A.P. in place of orig. rock, & in M.O.S.  
M.O.S. S38°E, 9.2 ft.  
M.O.S. N38°W, 8.7 ft.  
M.O.S. S46°W, 9.4 ft.  
M.O.S. N46°E, 10.5 ft.

T8S R44E  
S26 S25  
S35 S36  
1986  
LS 1658

FILED Aug. 11, 1986  
BAKER COUNTY SURVEYOR  
SURVEY NO. 8-44-145

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR  
*Ronald H. Schulson*  
OREGON  
RONALD H. SCHULSON  
1968

J & R No. 58617  
PREPARED FOR AND AT THE REQUEST OF  
WALLOWA-WHITMAN NATIONAL FOREST  
J & R SURVEYORS  
PO. BOX 418, DALLAS, OR 97338  
TELEPHONE: (503) 623-4003  
DATE: 7-25-86  
CONTRACT NO. 53-04H1-4-9624N  
ALL 1/4 SEC. 12, T. 8 S., R. 44 E., W.M., BAKER COUNTY