C 1/4 cor. of sec. 36, T7S, R44E

HISTORY OF ORIGNIAL CORNER ESTABLISHMENT:

Corner established by Barry B. Barbour, LS 1051, as described by Survey No. 7-44-171, filed November 7, 1985, in the records of the Baker County Surveyor. A Survey Resolution Agreement (Survey No. 7-44-227), filed on September 11, 1990, subsequently CANCELLED several Barry Barbour surveys including No. 7-44-77.

Barbour's cancelled corner record states: At surveyed point set 21/2" x 30" galvanized pipe and brass cap marked (as shown below): Set pipe 8" in the ground to bedrock and mound of stone around to cap. From which by magnetic declination of N20°E: A 14" Pine bears N65°E, 11.5 ft. scribed C 1/4 S36 BT.

A 12" Pine bears S67°W, 39.7 ft. scribed C 1/4 S36 BT. Placed 54-2 and 54-9 on a steel fence post 5' north and placed 54-2 on a steel fence post 5' south of the corner.

DESCRIPTION OF CORNER EVIDENCE FOUND:

ACCEPT the position monumented by Barry B. Barbour, during Survey 7-44-77, CANCELLED, as in practical agreement (±N. 42° E., ±0.5 ft. dist.) from a properly proportion position, holding the existing corners of the section as previously

T75 R44E

C1/4 --- S36

OR PLS 1051

Found iron pipe 2½ ins. diam., firmly set, projecting 22 ins. above ground, with a 3 ft. diam. mound of stone, and a 21/2 ins. diam. brass cap mkd. as shown. From the recovered monument I find the Barbour bearing trees;

A ponderosa pine, 20 ins. diam., alive and healthy, bears N. 65° E., 11.5 ft. dist., with healed double blaze. A ponderosa pine, 19 ins. diam., alive and healthy, bears S. 67° W., 39.7 ft, dist., with healed double blaze.

Found guard post 5 ft. S'iy with Property Boundary (54-2) sign and 6 ft. N'ly with Land Survey Monument (54-9) and Property Boundary (54-2) signs.

DESCRIPTION OF MONUMENT AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATION OF THIS CORNER:

Rebuild stone mound to top.

A 2 ins. BXO chiseled in NW face of exposed rock, 12 ins. high x 2 ft, wide x 2.5 ft. deep, bears S. 6° E., 43.1 ft. dist.

A 2 ins. BXO chiseled in SE face of exposed rock, 18 ins, high x 2 ft, wide x 1 ft. deep, bears N. 651/2° W., 24,0 ft. dist.

Auto C/A geographic position: Lat. 44°54'46.6" N Long. 117°16'23.0" W

Witnesses, Gail Walter, Kristina Powell, Brenda Johnson, and Jon Howells



CN 1/16 cor. of sec. 36, T7S, R44E

HISTORY OF ORIGNIAL CORNER ESTABLISHMENT:

Corner established by Barry B. Barbour, LS 1051, as described by Survey No. 7-44-158, filed November 7, 1985, in the records of the Baker County Surveyor. A Survey Resolution Agreement (Survey No. 7-44-227), filed on September 11, 1990, subsequently CANCELLED several Barry Barbour surveys including No. 7-44-77.

Barbour's cancelled corner record states: At surveyed point set 21/2" x 30" galvanized pipe and brass cap marked (as shown below): Set pipe 26" in the ground and mound of stone around to cap. From which by magnetic declination of N20°E: An 8" Pine bears S14°E, 82.0 ft scribed CN 1/16 S36 BT. A 15" Pine bears S61°W, 45.8 ft, scribed CN 1/16 S36 BT,

Placed 54-2 and 54-9 on a steel fence post 5' east and placed 54-2 on a steel fence post 5' south of the corner.

DESCRIPTION OF CORNER EVIDENCE FOUND:

ACCEPT the position monumented by Barry B. Barbour, during Survey 7-44-77. CANCELLED, as in practical agreement (±N. 59° W., ±0.1 ft. dist.) from a properly proportion position, holding the existing corners of the section as previously established.

Found iron pipe 2½ ins. diam., firmly set, projecting 6 ins. above ground, with a rock collar, and 21/2 ins. diam. brass cap mkd. as shown.

From the recovered monument I find the Barbour bearing trees: A ponderosa pine, 13 ins. diam., alive and healthy, bears S. 14° E., 82.0 ft. dist., with illegible scribe marks visible on partially healed double blaze.

A ponderosa pine, 20 ins. diam., alive and healthy, bears S. 61° W., 54.8 ft. dist., with illegible scribe marks visible on partially healed double blaze, and washer

in bottom blaze (Barbour: 45.8 ft.). Found quard post 5 ft. S'ly with Property Boundary (54-2) sign and 5 ft. W'ly with Land

Survey Monument (54-9) and Property Boundary (54-2) signs. DESCRIPTION OF MONUMENT AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATION OF THIS CORNER:

Auto C/A geographic position: Lat. 44°54'55.3" N

Witnesses: Ron Walter and Brenda Johnson

Long. 117°16'23.6" W

1/4 cor. of secs. 25 and 36, T7S, R44E

HISTORY OF ORIGNIAL CORNER ESTABLISHMENT:

Original corner set by W. B. Barr, under GLO Contract No. 503, approved March 21, 1885.

Record states: Set sandstone 16x12x10 ins. 11 inches in ground for 1/4 sec. cor, marked 1/4 on the N. side. Raised mound of rock alongside: pits impracticable Subsequent Monumentation:

Corner reestablished by Barry B. Barbour, LS 1051, as described by Survey No. 7-44-148, filed November 7, 1985, in the records of the Baker County Surveyor, A Survey Resolution Agreement (Survey No. 7-44-227), filed on September 11, 1990, subsequently CANCELLED several Barry Barbour surveys including No. 7-44-77.

continues in next column:

T7S R44E

N1/16

OR PLS 1051

continued from previous column:

Barbour's cancelled corner record states: Found no trace of record stone or mound of stone. Corner falls on rocky west slope and there are several skid roads in the area. No large trees or stumps near this area. Area has been searched by others, as lots of rocks have been turned over.

At surveyed point set 21/2" x 30" galvanized pipe and brass cap marked (as shown below): Set pipe 24" in the ground and mound of stone around to cap. From which by magnetic declination of N20°E;

A 16" Pine bears N21°E, 28.7 ft. scribed 1/4 S25 BT. A 20" Pine bears S26°E, 5.6 ft, scribed 1/4 S36 BT.

Placed 54-2 and 54-4 on a steel fence post 5' east and placed 54-2 on a steel fence post 5' west of the corner

BLM Group 2086, accepts Barbour's method for reestablishment of this corner position.

DESCRIPTION OF CORNER EVIDENCE FOUND:

ACCEPT the position monumented by Barry B. Barbour, during Survey 7-44-77, CANCELLED, as in practical agreement (±S. 71° E., ±0.6 ft. dist.) from a properly proportion position, as further described in narrative.

Found iron pipe 2½ ins. diam., firmly set, projecting 10 ins. above ground, with 3 ft. diam, mound of stone to top, and 21/2 ins. diam, brass cap, mkd, as shown,

From the recovered monument I find the Barbour bearing trees: A ponderosa pine, 21 ins. diam., alive and healthy, bears N. 21° E., 28.7 ft. dist, with illegible scribe marks visible on partially open double blaze. A ponderosa pine, 29 ins. diam., alive and healthy, bears S. 26° E., 5.6 ft. dist., with healed double

Found guard post ±5 ft. NE'ly with Land Survey Monument (54-9) and Property Boundary(54-2) signs, and ±10 ft W'ly with Property Boundary (54-2) sign.

DESCRIPTION OF MONUMENT AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATION OF THIS CORNER:

A ponderosa pine, 6 ins. diam., bears S, 43° W., 74.9 ft. dist., mkd. X BT. A ponderosa pine, 9 ins. diam., bears N. 111/4° W., 42.9 ft, dist., mkd. 1/4 S25 BT. Auto C/A geographic position:

Lat. 44°55'03.9" N Long. 117°16'20.9" W

Witnesses: Ron Walter and Brenda Johnson

(P)>

CS 1/16 cor. of sec. 25, T7S, R44E

HISTORY OF ORIGNIAL CORNER ESTABLISHMENT:

Corner established by Barry B. Barbour, LS 1051, as described by Survey No. 7-44-140, filed November 7, 1985, in the records of the Baker County Surveyor. A Survey Resolution Agreement (Survey No. 7-44-227), filed on September 11, 1990, subsequently CANCELLED several Barry Barbour surveys including No. 7-44-77.

Barbour's cancelled corner record states: At surveyed point set 21/2" x 30" galvanized pipe and brass cap marked (as shown below): Set pipe 25" in the ground. No rock in the area. From which by magnetic declination of N20°E An 11" Fir bears S88°E, 10.1 ft, scribed CS 1/16 S25 BT.

A 14" Fir bears S14°E, 17.2 ft. scribed CS 1/16 S25 BT. Placed 54-2 and 54-9 on a steel fence post 5' north and placed 54-2 on a steel fence post 5' west of the corner.

DESCRIPTION OF CORNER EVIDENCE FOUND:

ACCEPT the position monumented by Barry B. Barbour, during Survey 7-44-77, CANCELLED, as in practical agreement (±S, 89° W, ±0.4 ft. dist.) from a properly proportion position, holding the existing corners of the sections previously established. T7S R44E

Found iron pipe 2½ ins. diam., firmly set, projecting 2 ins. above ground, and 21/2 ins. diam, brass cap mkd. as shown. From the recovered monument I find the Barbour bearing trees; A Douglas fir, 16 ins. diam., alive and healthy, bears S. 88° E., 10.1 ft. dist., with healed blaze, washer

mkd. LS1051 in bottom of blaze. A Douglas fir, 19 ins. diam., alive and healthy, bears S. 14° E., 17,2 ft, dist., with healed blaze.

Found guard post 6 ft. W'ly with Property Boundary (54-2) sign and 6 ft. N'ly with Land Survey Monument (54-9) and Property Boundary (54-2) signs.

DESCRIPTION OF MONUMENT AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATION OF THIS CORNER:

Auto C/A geographic position:

Lat. 44°55'20.5" N Long. 117°16'21.9" W

Witnesses: Ron Walter and Brenda Johnson

28>

C 1/4 cor. of sec. 25, T7S, R44E

HISTORY OF ORIGNIAL CORNER ESTABLISHMENT:

Corner established by Barry B. Barbour, LS 1051, as described by Survey No. 7-44-133, filed November 7, 1985, in the records of the Baker County Surveyor. A Survey Resolution Agreement (Survey No. 7-44-227), filed on September 11, 1990,

subsequently CANCELLED several Barry Barbour surveys including No. 7-44-77. Barbour's cancelled corner record states. At surveyed point set 21/2" x 30" galvanized pipe and brass cap marked (as shown below): Set pipe 26" in the ground and mound of stone around to cap. From which by magnetic declination of N20°E: An 18" Pine bears S09°E, 75.4 ft. scribed C 1/4 S25 BT.

A 14" Pine bears N89°W, 48.6 ft. scribed C 1/4 S25 BT. Placed 54-2 and 54-9 on a steel fence post 5' north and placed 54-2 on a steel fence post 5' south of the corner.

continues in next column:

S1/16 | S25

OR PLS 1051

continued from previous column:

DESCRIPTION OF CORNER EVIDENCE FOUND:

I ACCEPT the position monumented by Barry B. Barbour, during Survey 7-44-77, CANCELLED, as in practical agreement (±S. 63° W., ±0.3 ft. dist.) from a properly proportion position, holding the existing corners of the section as previously

T7S R44E

C1/4 — S25

OR PLS 1051

Found iron pipe 2½ ins, diam., firmly set, projecting 4 ins. above ground, with a rock collar, and a 21/2 ins. diam. brass cap mkd. as shown.

From the recovered monument I find the Barbour bearing A ponderosa pine, 25 ins. diam., alive and healthy, bears

S. 9° E., 75.4 ft. dist., with healed double blaze. Pine remains, bears N. 89° W., 48.6 ft. dist, with scribe marks BT and washer mkd. LS 1051 visible in lower

Found guard post 5 ft. S'ly with Property Boundary (54-2) sign and 4 ft. N'ly with Land Survey Monument (54-9) and Property Boundary (54-2) signs.

DESCRIPTION OF MONUMENT AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATION OF THIS CORNER:

A ponderosa pine, 12 ins. diam., bears N. 77° E., 7.0 ft. dist., mkd. C 1/4 S25 BT. A ponderosa pine, 11 ins. diam., bears S. 42° W., 74.9 ft. dist, mkd C 1/4 S25 BT.

A ponderosa pine, 16 ins. diam., bears N. 521/2° W., 64,8 ft. dist., mkd C 1/4 S25 BT. Auto C/A geographic position: Lat. 44°55'36.8" N

Long. 117°16'23.3" W Witnesses: Ron Walter and Brenda Johnson

29>

T7S R44E

OR PLS 1051

1/4 cor. of secs. 24 and 25, T7S, R44E

HISTORY OF ORIGNIAL CORNER ESTABLISHMENT:

Original corner set by W. B. Barr, under GLO Contract No. 503, approved March 21, 1885.

Record states: Set basalt rock 10x10x8 ins. 7 inches in ground for 1/2 sec., cor. marked 1/4 on the N. side, from which: A fir 30 ins. diam. bears N40°E, 35 lks, dist, marked 1/4SBT.

A fir 8 ins. diam, bears S32°W, 60 lks, dist, marked 1/4SBT.

Subsequent Monumentation:

Corner remonumented by Lester E. Fischer, under BLM Group No. 350, approved

Record States: The 1/4 sec. cor. of secs. 24 and 25, determined at record bearing and distance from the remains of the original bearing trees. A decayed ponderosa pine stump, 18 ins. diam., bears S, 32° W., 60 ks. dist. with

scribe marks 1/4 S BT visible on opened blaze. (Record, fir) At the corner point. Set an iron post, 28 ins. long, 21/2 ins. diam., 22 ins. in the ground, with brass cap mkd. (as shown below). from which new bearing trees:

A white fir, 12 ins. diam., bears S. 32° E., 32 lks. dist., mkd. 1/4 S25 BT. A ponderosa pine, 11 ins, diam., bears N. 61° W., 50 lks, dist., mkd. 1/4 S24 BT.

DESCRIPTION OF CORNER EVIDENCE FOUND: Found an iron pipe 21/2 ins. diam. by 30 ins. long,

projecting 6 ins. out of ground, with 31/4 ins. diam.brass cap mkd, as shown. From the recovered monument I find the original bearing tree remains:

Decayed stump, bears S. 32° W., 60 lks. dist., with scribe 1/4SBT alongside. And accessories mkd. by Fischer: A white fir, 23 ins. diam., alive and healthy, bears

S. 32° E., 32 lks. dist., with healed blaze. A ponderosa pine, 20 ins. diam., alive and healthy, bears N. 61° W., 50 lks. dist., with healed blaze. Found guard post 5 ft. S'ly with Property Boundary (54-2) and Attention (54-4) signs and 6 ft. Wly with Property

DESCRIPTION OF MONUMENT AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATION OF THIS CORNER:

New bearing trees: A white fir, 7 ins. diam., bears S. 611/4° W., 22.6 ft. dist., mkd. 1/4 S25 BT. A white fir, 6 ins. diam., bears N. 3° W., 14.8 ft. dist., mkd. X BT. No suitable trees within reasonable distance in the NE quadrant

Monument is ±50 ft. Wly of FS Rd No. 375 on E-facing slope. Auto C/A geographic position: Lat. 44°55'55,7" N Long 117°16'21.4" W

Boundary (54-2) sign.

Witnesses: Gail Walter, Kristina Powell, Brenda Johnson and Jon Howells

NE 1/16 cor. of sec. 36, T7S, R44E

HISTORY OF ORIGNIAL CORNER ESTABLISHMENT:

Corner established by Barry B. Barbour, LS 1051, as described by Survey No. 7-44-159, filed November 7, 1985, in the records of the Baker County Surveyor. A Survey Resolution Agreement (Survey No. 7-44-227), filed on September 11, 1990,

subsequently CANCELLED several Barry Barbour surveys including No. 7-44-77, Barbour's cancelled corner record states: At surveyed point set 21/2" x 30" galvanized pipe and brass cap marked (as shown below): Set pipe 18" in the ground and mound of stone around to cap. From which by magnetic declination of N20°E:

A 15" Pine bears S42°E, 64.1 ft. scribed NE 1/16 S36 BT A 12" Pine bears S85°W, 5.3 ft. scribed NE 1/16 S36 BT. Placed 54-2 and 54-9 on a steel fence post 5' south and placed 54-2 on a steel

DESCRIPTION OF CORNER EVIDENCE FOUND:

fence post 5' west of the corner.

ACCEPT the position monumented by Barry B. Barbour, during Survey 7-44-77, CANCELLED, as in practical agreement (±S. 50° W., ±0.4 ft. dist.) from a properly proportion position, holding the existing corners of the section as previously established.

Found iron pipe 21/2 ins. diam., firmly set, projecting 12 ins

above ground, with 3 ft. diam, mound of stone to top, and 21/2 ins. diam. brass cap mkd. as shown. From the recovered monument I find the Barbour bearing tree/remains:

A ponderosa pine snag, 15 ins. diam., bears S. 42° E. 64.1 ft, dist, with scribe marks NE 1/16 S36 BT visible on open double blaze, washer coated in pitch in bottom of blaze, with broken top alongside.

A ponderosa pine, 17 ins. diam., alive and healthy, bears S. 85° W., 5.3 ft. dist., with scribe marks E 1/16 S36 BT visible on partially open double blaze, and washer mkd_PLS 1051 in lower blaze.

Found guard post 5 ft. N'ly with Land Survey Monument (54-9) and Property Boundary

DESCRIPTION OF MONUMENT AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATION OF THIS CORNER:

New bearing tree:

A ponderosa pine, 11 ins. diam., bears S. 831/2° E., 60.1 ft. dist., mkd. NE 1/16 S36 BT. Auto C/A geographic position: Lat. 44°54'58.8" N

Long. 117°16'10.6" W Witnesses: Ron Walter and Brenda Johnson

tree/remains:

E 1/16 cor. of secs. 25 and 36, T7S, R44E

HISTORY OF ORIGNIAL CORNER ESTABLISHMENT:

Corner established by Barry B. Barbour, LS 1051, as described by Survey No. 7-44-149, filed November 7, 1985, in the records of the Baker County Surveyor. A Survey Resolution Agreement (Survey No. 7-44-227), filed on September 11, 1990, subsequently CANCELLED several Barry Barbour surveys including No. 7-44-77.

Barbour's cancelled corner record states: At surveyed point set 21/2" x 30" galvanized pipe and brass cap marked (as shown below): Set pipe 25" in the ground and mound of stone around to cap. From which by magnetic declination of N20°E:

A 10" Pine bears S23°E, 40.2 ft scribed E1/16 S36 BT. A 16" Pine bears S84°W, 16.7 ft, scribed E1/16 S25 BT Placed 54-2 and 54-9 on a steel fence post 5' south and placed 54-2 on a steel fence post 5' west of the corner.

DESCRIPTION OF CORNER EVIDENCE FOUND:

I ACCEPT the position monumented by Barry B. Barbour, during Survey 7-44-77, CANCELLED, as in practical agreement (±S, 17° E,, ±0.8 ft, dist.) from a properly proportion position, as further described in narrative.

Found iron pipe 2½ ins. diam., firmly set, projecting 6 ins. above ground, with rock collar, and 21/2 ins, diam. brass cap mkd, as shown. From the recovered monument I find the Barbour bearing

A ponderosa pine stump, bears S. 23° E., 40.2 ft. dist., with dead and down tree alongside. A ponderosa pine, 24 ins. diam,, alive and healthy, bears S. 84°W., 16.7 ft. dist., with healed double blaze. Found guard post 5 ft. S'ly with Land Survey Monument (54-9) and Property Boundary (54-2) signs and 5 ft.

SW'ly with Property Boundary (54-2) sign.

T7S R44E S25 E - | - 1/16 OR PLS 1051 1981

17S R44E

1/16 —— S36

OR PLS 1051

DESCRIPTION OF MONUMENT AND ACCESSORIES ESTABLISHED TO PERPETUATE LOCATION OF THIS CORNER:

A Douglas fir, 6 ins. diam., bears S. 44%° E., 20.8 ft. dist., mkd. X BT. Auto C/A geographic position: Lat. 44°55'09.3" N Long. 117°16'10.5" W

Witnesses: Ron Walter and Brenda Johnson

T7S R44E

1974

Ran Walter **OREGON** RON C. WALTER 2648

REGISTERED

PROFESSIONAL

LAND SURVEYOR

FILED Nov. 25 , 2013 BAKER COUNTY SURVEYOR

> 8-44-159 7-45-167 8-45-148

Record of Survey Wallowa-Whitman National Forest

LOCATED WITHIN Secs. 25, 26, 35 and 36 Township 7 South, Range 44 East Willamette Meridian, Baker County, Oregon

★ Wallowa Associates 303 S.E. Alamo Street Enterprise, Oregon 97828

(541) 426-9049 SCALE SHEET No. DATE OF SURVEY Beginning: May 7, 2013 7 of 8 Ending: August 7, 2013 CHECKED PROJECT No. DRAWN BY RCW/KLP/BMJ WA 1091-06/2318 RCW DATE 11/2013

Renewal Date: June 30, 2014

SURVEY NO. 7-44-264