


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Nicolas O. Walden made the original survey under Contract No. 198, dated July 15, 1873. At the section corner location common to sections 31, 32 & 5, 6, T 8 & 9 S, R 45 E, he set a basalt rock 16 x 8 x 8, 8" in ground.



Description of corner evidence found:

At the above mentioned section corner I found a basalt stone 17 x 9 x 8 on the surface in a small mound of stone. No markings were visible on the stone. No other evidence was in area and large rock was limited to corner only.

Description of monument and accessories I established to perpetuate the original location of this corner

At the section corner location I set a 2" x 30" galv. iron pipe with a brass cap approx. 18" above surface of ground as area is gravelly. I then placed original stone on the north side of the monument and then made a large mound of stone 3½ft. dia. and 3 ft. high covering the monument and the original stone. There are no accessories available.

Cap stamped:
 T 8 S
 S 31 | S 32
 S 6 | S 5
 T 9 S R 45 E
 1980
 ORLS 645

REGISTERED
 PROFESSIONAL
 LAND SURVEYOR

James H. Hambleton

4-9-80

OREGON
 JULY 15, 1964
 JAMES H. HAMBLETON
 645

Office of County of
 State of, I hereby certify that the within instrument was filed in this office
 for record on the day of
 by
 (COUNTY OFFICIAL) (DEPUTY)

FILED 4-9-80
 BAKER COUNTY SURVEYOR
 SURVEY NO. 8-45-5