


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

W.B. Barr made the original survey under Contract No. 355, dated June 14, 1880. At the section corner location common to Sections 29, 30, 31 & 32, T 8 S R 45 E, he set a marked basalt rock 14" x 10" x 8".



Description of corner evidence found:

At the above mentioned section corner location, I found a basalt stone 14 x 10 x 7 in a mound of stone and being marked with 1 notch on the south face and 5 notches on the east edge.

Description of monument and accessories established to perpetuate the original location of this corner

At the section corner location I set a 2" x 30" galv. iron pipe with a brass cap approx. 20" above surface as ground very rocky. Set the original stone along the west edge of the iron pipe in a large mound of stone approx. 4 ft. dia. and 2 ft. high. There was no accessories available.

Cap stamped:

T 8 S  

S 30	S 29
S 31	S 32

R 45 E  
1980  
ORLS 645

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*James H. Hambleton*  
4-9-80

OREGON  
JULY 20, 1963  
JAMES H. HAMBLETON  
645

Office of ..... County of .....  
State of ....., I hereby certify that the within instrument was filed in this office  
for record on the ..... day of .....

..... by .....  
(COUNTY OFFICIAL) (DEPUTY)

FILED 4-9-80  
BAKER COUNTY SURVEYOR  
SURVEY NO. 8-45-10