


B-17 785 R45E

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment: *NONE*



Description of corner evidence found: *NONE*

Description of monument and accessories I established to perpetuate the original location of this corner: *AT CALCULATED POSITION I SET A 2" x 30" GALV. IRON PIPE W/BRASS CAP STAMPED AS SHOWN, FROM WHICH:*

*NEW BT, 8" PINE, SCRIBED "N  $\frac{1}{16}$  S 3 BT" BEARS N 77° W, 15.6 FT.  
NEW BT, 14" FIR, SCRIBED "N  $\frac{1}{16}$  S 2 BT" BEARS N 52° E, 9.9 FT.*

*I SET THE 2" PIPE 27" W GROUND AND SET STONES AROUND IT.*

*I SET A STEEL POST 3' S. OF COR W/SIGN 54-2, AND A STEEL POST 3' W. OF CORNER W/SIGNS 54-2 & 54-9.*

*I PRINTED A RED BAND AROUND BOTH BT'S, AND TAGGED THEM W/SIGN 54-3*

*I HEREBY CERTIFY THE ABOVE CORNER MONUMENT WAS ESTABLISHED AS HEREIN DESCRIBED ON JUNE 6, 1980*

*WITNESS: Doug McFend*

REGISTERED PROFESSIONAL LAND SURVEYOR

*Victor M. McFend*

OREGON JULY 17, 1970 VICTOR M. MCLIND 934

Office of..... County of.....  
State of..... I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....  
..... by .....  
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

FILED Aug. 11, 1980  
BAKER COUNTY SURVEYOR  
SURVEY NO. 8-45-18

GPO-798-276

*Doug*