


D 13 TBS R45E

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment: *NONE*



Description of corner evidence found: *NONE*

Description of monument and accessories I established to perpetuate the original location of this corner: *AT CALCULATED POSITION I SET A 2" X 30" GALV IRON PIPE W/BRASS CAP STAMPED AS SHOWN ABOVE, FROM WHICH:*

*NEW BT, 17" PINE, SCRIBED "S 1/6 S.4 BT" BEARS S 30° W, 124.5 FT.  
NEW BT, 15" PINE, SCRIBED "S 1/6 S.3 BT" BEARS N 27 3/4° E, 81.0 FT.*

*I SET THE 2" PIPE 28" IN GROUND AND SET STONES AROUND IT.  
I SET A STEEL POST 3' E. OF COR. W/SIGNS 54-2 & 54-9, AND A STEEL POST 3' S. OF COR. W/SIGN 54-2  
I PAINTED A RED BAND AROUND BOTH BT'S, AND TAGGED THEM W/SIGN 54-3*

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Victor M. McLind*

OREGON  
JULY 17, 1970  
VICTOR M. McLIND  
934

*I HEREBY CERTIFY THE ABOVE CORNER MONUMENT WAS ESTABLISHED AS HEREIN DESCRIBED ON JUNE 12, 1980.*

*WITNESS: Doug McLeod*

Office of..... County of.....  
State of....., I hereby certify that the within instrument was filed in this office  
for record on the..... day of....., 19.....  
..... by .....

(COUNTY OFFICIAL)

(DEPUTY)

Form R6-7100-57 (9/71)

FILED Aug. 11, 1980  
BAKER COUNTY SURVEYOR  
SURVEY NO. 8-4S-24

☆ GPO—798-276