


D-14 TBS R45E

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment: *NONE*



Description of corner evidence found: *NONE*

Description of monument and accessories I established to perpetuate the original location of this corner: *AT CALCULATED POSITION I SET A 2" X 30" GALV. IRON PIPE W/ BRASS CAP STAMPED AS SHOWN ABOVE, FROM WHICH:*

*NEW BT, 17" FIR, SCRIBED "SW $\frac{1}{16}$ S3 BT" BEARS N43°E, 16 FT.
NEW BT, 10" FIR, SCRIBED "SW $\frac{1}{16}$ S3 BT" BEARS N89 $\frac{1}{2}$ °E, 632 FT.*

*I SET THE 2" PIPE 27" IN GROUND AND SET STONES AROUND IT.
I SET A STEEL POST 3' N. OF COR. W/ SIGN 54-2, AND A STEEL POST 3' W. OF COR. W/ SIGNS 54-2 & 54-9.
I PAINTED A RED BAND AROUND BOTH BT'S, AND TAGGED THEM W/ SIGN 54-3*

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Victor M. McLeod

OREGON
JULY 17, 1970
VICTOR M. MCLIND
934

I HEREBY CERTIFY THE ABOVE CORNER MONUMENT WAS ESTABLISHED AS HEREIN DESCRIBED ON JUNE 11, 1980.

WITNESS: Doug McLeod

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....
..... by
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

FILED Aug 11, 1980
BAKER COUNTY SURVEYOR
SURVEY NO. 8-4S-25