


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment: CORNER ESTABLISHED BY
BARIN & WALDEN UNDER GLO. CONTRACT IN 1873
SURVEYOR GENERAL'S RECORDS STATE: SET BASALT
ROCK 12x9x7 FOR CORNER TO SECS. 31, 32, 5
AND 6.



Description of corner evidence found: NONE

Description of monument and accessories I established to perpetuate the
original location of this corner: AT PROPORTIONED LOCATION I SET A 2"x30" GALV. IRON
PIPE W/ BRASS CAP STAMPED AS SHOWN ABOVE, FROM WHICH:
NEW BT, 6" FIR, SCRIBED "T88 R45E S6 BT" BEARS S24 1/4 W, 12.2 FT.
NEW BT, 10" FIR, SCRIBED "T75 R45E S31 BT" BEARS N29 W, 18.2 FT.
NEW BT, 10" FIR, SCRIBED "T75 R45E S32 BT" BEARS N 60 3/4 E, 29.1 FT.
NEW BT, 8" FIR, SCRIBED "T88 R45E S5 BT" BEARS S30 1/2 E, 20.2 FT.
I SET THE 2" PIPE 28" IN GROUND AND SET STONES AROUND IT.
I SET A STEEL POST 3' W OF COR. W/SIGN 54-4
I PAINTED A RED BAND AROUND ALL BT'S AND TAGGED THEM W/SIGN 54-3

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Victor M. McLind

OREGON
JULY 17, 1970
VICTOR M. McLIND
934

I HEREBY CERTIFY THE ABOVE CORNER MONUMENT WAS
RE-ESTABLISHED AS HEREIN DESCRIBED ON JUNE 25,
1980.

WITNESS: *Doug McFerd*

Office of..... County of.....
State of..... I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....
..... by