


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

0359

History of original corner establishment:

Corner original established by W. B. Barr under contract No. 355 dated June 14 1880. Marked basalt rock 15"X10"X5" for 1/4 sec. corner. Raised mound of rocks as per instructions.



Description of corner evidence found:

At the corner I found a 15"X10"X5" rock in a mound of rock with a faint 1/4 marked on face. No accessories set.

Description of monument and accessories I established to perpetuate the original location of this corner:

I reset the corner in its original position- I set a 3"X30" Aluminum Capped Aluminum pipe 6" in the ground in a mound of rock 5'X24" from which
 A 22" Ponderosa Pine bears N 46° 45" E 62.55 ft.
 Marked 1/4 S7 BT Nail in N. base.
 A 4'X3'X18" rock bears S 59° 15' E 77.08 ft.
 Marked Chiseled "X" on south top.

Bearings taken with a staff compass declination 18 1/2 East per 1980 isogonic chart. Distances are pulled to 60d nails with brass washers stamped L.S. 1898 driven in the side center of Bearing Trees.

MONUMENT STAMPED

T 8 S
 R 45 7 1/4 COR.
 E 18
 OR. L.S. 1898
 1982



Office of..... County of Baker
 State of Oregon..... I hereby certify that the within instrument was filed in this office
 for record on the..... day of....., 19.....
 by
 (COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

FILED June 22, 1982
 BAKER COUNTY SURVEYOR
 SURVEY NO. B-45-50

J-03
 ☆ GPO-798-276