


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Original exterior boundary line survey executed by N. O. Walden in October 1873 under Contract No. 198, dated July 15, 1873. Original subdivisional survey was executed by W. B. Barr in September 1880 under contract No. 355, dated June 14, 1880.

Set basalt rock 24"x12"x12" in mound of rock.



Description of corner evidence found:

NONE

Description of monument and accessories I established to perpetuate the original location of this corner:

Set 30" long aluminum pipe with 3 1/4" aluminum cap, marked as shown above, 6" above ground. Steel post with sign 54-9 set next to cap.

Scribed:

16" pine S.22°E. 90.0' "1/4 S1 BT"

Attached signs 54-3 & 54-9 and nailed aluminum washer stamped "RLS 1928" by "BT scribe on tree. Painted blaze red and a 6" red band around tree.

REGISTERED
PROFESSIONAL
LAND SURVEYOR
1-20-86
Duane Fehringer
OREGON
JULY 13, 1984
DUANE FEHRINGER
2118

Office of..... County of.....
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....
..... by

(COUNTY OFFICIAL)

(DEPUTY)

FILED May 9, 1986
SARER COUNTY SURVEYOR
SURVEY NO. 8-45-66