

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

R-21


History of original corner establishment:

Corner established by W.B.Barr under GLO contract no. 358 dated June 14, 1880.

Surveyor General records state:

Marked basalt rock 15 x 10 x 8" for corner to secs 23,24,25 & 26.
Raised mound of rock as per instructions.

Corner recovered by USDI-BLM in 1983 during course of performing work authorized by Special Instructions dated August 4, 1983 under Group No. 1169, Oregon.



Description of corner evidence found:

Found: A basalt stone 13"x8"x7" (record states 15 x 10 x 8") loose on the ground with 2 notches and 1 notch marked on adjacent edges and with a steel fence post alongside and BLM location tag under stone by WKD dated 1983.


Description of monument and accessories I established to perpetuate the original location of this corner:

At position of found stone...Set an 2 1/2" aluminum cap on 2" aluminum pipe 30" long 20" in the ground to bedrock with 10" projecting out of ground with surrounding rock mound and attached sign 54-9 to fence post alongside. Buried original stone alongside aluminum monument.

There being no suitable trees within limits, I marked the following bearing object... A basalt boulder 40"x 24" x 20" bears N71°E, 111.5' dist marked "BXO"...and there being no other suitable bearing objects available within limits I established the following reference monument...A 5/8" x 30" rebar driven "to refusal" bears N54°W, 26.1' dist with a 1 1/2" diam aluminum cap attached and marked thus:

Compass declination 20° East.

I hereby certify that the above described corner monument was properly established by me on March 16, 1987.



REGISTERED PROFESSIONAL LAND SURVEYOR

William L Hanley

OREGON
JULY 14, 1978
WILLIAM L. HANLEY
1639

Office of..... County Surveyor..... County of..... Baker.....

State of..... Oregon....., I hereby certify that the within instrument was filed in this office for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL) (DEPUTY)

FILED 4/15/87
COUNTY SURVEYOR
SURVEY NO. 8/45/87