



NARRATIVE OF SURVEY

THIS DEPENDENT SUBDIVISIONAL SURVEY OF SECTION 10, T.8S., R.4SE., W.M., WAS PERFORMED BY WILLIAM L. HANLEY, ORLS 1639, AT THE REQUEST OF THE U.S.D.A. FOREST SERVICE FOR THE PURPOSE OF MONUMENTING CERTAIN OWNERSHIP AND CONTROLLING CORNERS AND TO MARK THE CONNECTING LINES BETWEEN WHICH DELINEATE THE BOUNDARY BETWEEN PRIVATE OWNERSHIP AND THOSE LANDS OF THE PUBLIC DOMAIN ADMINISTERED BY THE U.S.D.A. FOREST SERVICE. THE WEST AND NORTH LINES OF SECTION 10 WERE PREVIOUSLY RESURVEYED BY VICTOR M. LIND, ORLS 934, AS NOTED IN THE ACCOMPANYING LEGEND AND HISTORY OF SURVEYS AND THE NORTHWEST CORNER OF THE NE 1/4 AND NORTH WEST CORNER OF THE NE 1/4 ESTABLISHED DURING THAT SURVEY WERE ACCEPTED AS TRUE CORNERS. THE ORIGINAL EAST QUARTER SECTION CORNER TO SECTION 10 WAS NOT RECOVERED AFTER DILIGENT SEARCH AND SUBSEQUENTLY DECLARED LOST (DESTROYED BY CONSTRUCTION OF FOREST ACCESS ROAD NO. 7100) AND REESTABLISHED AT ITS SINGLE PROPORTIONATE POSITION MIDWAY BETWEEN THE ADJACENT NORTHEAST AND SOUTHEAST SECTION CORNERS.

CORNER MONUMENTS ESTABLISHED THIS SURVEY ARE 2 1/2 INCH ALUMINUM CAPS SECURELY ATTACHED TO 2 1/2 INCH DIAMETER ALUMINUM PIPES 30 INCHES LONG WITH FLARED LEGS. BOUNDARY LINES WERE ESTABLISHED BY OFFSET MEASUREMENT FROM SURVEY CONTROL POINTS AND MARKED WITH 6-FOOT LONG STEEL FENCE POSTS SPACED AT APPROXIMATELY 200-FOOT INTERVALS WITH USFS BOUNDARY SIGNS S4-2 ATTACHED. FIELD INSTRUMENTS USED WERE A 6-SECOND THEODOLITE AND ELECTRONIC DISTANCE METER CONTAINED IN A SINGLE UNIT MANUAL TOTAL STATION WITH ANGLES AND DISTANCES TAKEN TO REMOTE SINGLE OR TRIPLE PRISM ASSEMBLIES ATTACHED TO 4-FOOT TELESCOPING RANGE POLE PLUMBED WITH 2-LEG TRIPOD. BACKSIGHTS WERE TAKEN TO NAIL IN 4-FOOT LATH. MEASUREMENTS TO CORNER ACCESSORIES AND PHOTO IDENTIFICATION POINT WERE TAKEN WITH A STAFF COMPASS WITH 3-INCH NEEDLE AND STEEL TAPE.

SURVEYORS' CERTIFICATE

I, WILLIAM L. HANLEY, A REGISTERED LAND SURVEYOR IN THE STATE OF OREGON, DO HEREBY CERTIFY THAT THIS PLAT, AND THE CERTIFIED RECORD OF LAND CORNER MONUMENTATION CERTIFICATES ACCOMPANYING THIS PLAT, AND FILED SEPARATELY, IS A TRUE REPRESENTATION OF A SURVEY PERFORMED BY ME AT THE REQUEST OF THE U.S.D.A. FOREST SERVICE IN FULL CONFORMANCE WITH THE STATUTES OF THE STATE OF OREGON AND WITH THE ARTICLES OF MY CONTRACT.

William L. Hanley
OWNER: BILL HANLEY SURVEYING CO.
OREGON LICENSE NO. 1639

REGISTERED PROFESSIONAL LAND SURVEYOR

William L. Hanley

OREGON
JULY 14, 1978
WILLIAM L. HANLEY
1639

FILED May 13, 1987
BAKER COUNTY SURVEYOR
SURVEY NO. _____

LEGEND

- SET 2 1/2" x 30" ALUMINUM PIPE WITH 2 1/2" ALUMINUM CAP AT PROPORTIONED POSITION FROM TRAVERSE SURVEY CONTROL
- ⊗ SET 2 1/2" x 30" ALUMINUM PIPE WITH 2 1/2" ALUMINUM CAP FROM RECOVERED ORIGINAL EVIDENCE
- FOUND 2" x 30" GALV. IRON PIPE WITH 2 1/2" BRASS CAP BY VICTOR M. LIND, ORLS 934, RECORDED UNDER BAKER COUNTY SURVEY NO. 8-45-16 DATED AUG. 11, 1980.
- [] RECORD MEASUREMENTS BY VICTOR M. LIND, ORLS 934, RECORDED ON BAKER COUNTY SURVEY NO. 8-45-16.
- () RECORD OF ORIGINAL SURVEY PERFORMED BY W.B. BARR UNDER GLO SURVEY NO. 358 DATED JUNE 14, 1880.
- NATIONAL FOREST BOUNDARY MARKED THIS SURVEY
- - - NATIONAL FOREST BOUNDARY MARKED BY VICTOR M. LIND, ORLS 934, RECORDED ON PREVIOUSLY REFERENCED BAKER COUNTY SURVEY NO. 8-45-16.
- FOREST ACCESS ROAD

HISTORY OF SURVEYS

T.8S., R.4SE., W.M. WAS ORIGINALLY SUBDIVIDED BY W.B. BARR UNDER GLO CONTRACT NO. 358 DATED JUNE 14, 1880, DURING AUGUST AND SEPTEMBER, 1880.

THE NORTH AND WEST LINES OF SECTION 10, T.8S., R.4SE., W.M., WERE RETRACED BY VICTOR M. LIND, ORLS 934, UNDER U.S.D.A. (FOREST SERVICE) CONTRACT NO. 53-04H1-9-7537N. A RECORD OF SURVEY PLAT WAS SUBSEQUENTLY FILED WITH THE BAKER COUNTY SURVEY RECORDS UNDER SURVEY NO. 8-45-16.

JAMES HAMBLETON, ORLS 645, SEARCHED FOR SEVERAL ORIGINAL CORNERS IN THE IMMEDIATE AND SURROUNDING AREA UNDER U.S.D.A. (FOREST SERVICE) CONTRACT IN 1973, WITHOUT BENEFIT OF SURVEY CONTROL AND WITH MINIMAL RECOVERY.

NOTE FOR RECORD OF CORNER MONUMENTATION SEE CERTIFIED RECORD OF LAND CORNER MONUMENTATION FILED SEPARATELY.

RECORD OF SURVEY PLAT

STRINGER CADASTRAL SURVEY

USDA FOREST SERVICE CONTRACT NO. 53-04H1-6-0166N

SECTION 10, T.8S., R.4SE., W.M.

Surveyed April 25 to May 01, 1987

Scale 1" = 500'

SURVEYED BY: WILLIAM L. HANLEY, OWNER
BILL HANLEY SURVEYING CO.
3120 GRANDVIEW DR.
P.O. BOX 824
BAKER, OREGON 97814
(503) 523-4325

FIELD BOOK REFERENCES

FIELD BOOKS NO. 1 & 2, STRINGER CADASTRAL SURVEY

FILED May 13, 1987

BAKER COUNTY SURVEYOR
SURVEY NO. 8-45-106