

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

E-22

History of original corner establishment:

None. Corner established this survey.

DIAGRAM

T 8 S R 45 E

W $\frac{1}{16}$ S 1
S 12

1987

ORLS 1639

Description of corner evidence found:

None.

Description of monument and accessories I established to perpetuate the original location of this corner:

At position midway between adjacent quarter corner East and section corner West as determined by survey...

Set $2\frac{1}{2}$ " aluminum cap on 2" aluminum pipe 25" in ground with 5"
projecting out of ground with surrounding rock mound and 6' fence
post alongside with sign 54-9 & 54-2 attached. Cap marked as shown in diagram.

New bearing trees established:

Ponderosa pine 13" dia brs S 1° W, 87.8' dist marked 1/4S12 BT.

A poplar 8" dia brs N 68° E, 21.1' dist marked 1/4S1 BT(bark scribe).

Each BT has a sign 54-3 and signs 54-4 or 54-9 attached below a 6"
band of red paint, and each new BT has a brass washer marked PLS 1639
nailed flush with BT blaze.

Compass declination 19° East.

I hereby certify that the above described
corner monument was properly established
by me and witnessed by Jim DeMastus on
June 16, 1987.

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

William L. Hanley
OREGON
JULY 14, 1978
WILLIAM L. HANLEY
1639