

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Corner established by W. B. Barr under GLO contract No. 358 and dated June 14, 1880.

Surveyor General records state:

Set stake 4 ft long 4 ins diam 18 ins in ground for 1/4 Sec corner. Raised mound of rock as per instructions.

E-23

DIAGRAM

T 8 S R 45 E

$\frac{1}{4}$ $\frac{S}{S} \frac{1}{12}$

1987

ORLS 1639

Description of corner evidence found:

Did not find original corner post or rock mound after thorough and diligent search.

Description of monument and accessories established to perpetuate the original location of this corner:

At position midway between adjacent section corners East and West as determined by survey...

Set 2½" aluminum cap on 2" aluminum pipe 25" in ground with 5" projecting out of ground with surrounding rock mound and 6' fence post alongside with sign 54-9 attached. Cap marked as shown in diagram.

New bearing trees established:

Ponderosa pine 19" dia brs N31° E, 64.8' dist marked 1/4S1 BT.

A basalt rock 20 x 14" projecting 8" out of ground brs N86½° W, 42.3' dist marked BXO on its center top.

Each new BT has a band of red paint, painted blaze, a brass washer marked PLS 1639 nailed flush to BT blaze and signs 54-3 & 54-9 attached. Bearing object painted red.

Compass declination 20° East.

I hereby certify that the above described corner monument was properly re-established by me and witnessed by Jim DeMastus on June 16, 1987.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William L. Hanley

OREGON
JULY 14, 1978
WILLIAM L. HANLEY
1639

Office of County Surveyor County of Baker
State of Oregon I hereby certify that the within instrument was filed in this office
for record on the day of 19.....

(COUNTY OFFICIAL)

(DEPUTY)

Form R6-7100-57 (9/71)

FILED 12-3-87
BAKER COUNTY SURVEYOR
SURVEY NO. 8-45-109

GPO-791-311