


**CERTIFIED RECORD OF LAND CORNER MONUMENTATION**

J-24

**History of original corner establishment:**

None. Corner established this survey.



**Description of corner evidence found:**

None.

**Description of monument and accessories established to perpetuate the original location of this corner:**

At position midway between adjacent quarter corner West and section corner East as determined by survey....

Set 2½" aluminum cap on 2" aluminum pipe 25" in ground with 5" projecting out of ground with surrounding rock mound and 6' fence post alongside with sign 54-9 and 54-2. Cap marked as shown in diagram.

New bearing trees established:

Ponderosa pine 16" diam brs S01½°E, 86.7' dist marked E1/16S13 BT.

Ponderosa pine 22" diam brs N78½°W, 147.1' dist marked E1/16S12 BT.

Each BT has a sign 54-3 and sign 54-9 attached below a 6" band of red paint, and each new BT has a brass washer marked PLS 1639 nailed flush with BT blaze.

Compass declination 19° East.

I hereby certify that the above described corner monument was properly established by me and witnessed by Jim DeMastus on June 18, 1987.

**REGISTERED  
PROFESSIONAL  
LAND SURVEYOR**

*William L. Hanley*

OREGON  
JULY 14, 1978  
WILLIAM L. HANLEY  
1639

Office of..... County Surveyor..... County of Baker  
Oregon

State of..... I hereby certify that the within instrument was filed in this office  
for record on the..... day of....., 19.....

..... by .....

(COUNTY OFFICIAL)

(DEPUTY)