

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

N-24

**History of original corner establishment:**

None. Corner established this survey.

**DIAGRAM**

T 8 S R 45 E

E  $\frac{1}{16}$  S  $\frac{13}{24}$

1987

ORLS 1639

**Description of corner evidence found:**

None.

**Description of monument and accessories I established to perpetuate the original location of this corner:**

At position midway between adjacent quarter corner West and section corner East as determined by survey....

Set 2½" aluminum cap on 2" aluminum pipe 20" in ground with 10" projecting out of ground with surrounding rock mound and 6' fence post alongside with sign 54-9 attached. Cap marked as shown in diagram.

**New bearing trees established:**

White fir 13" diam brs N08°W, 21.5' dist marked E1/16S13 BT.  
Ponderosa pine 7" diam brs S60½°W, 83.5' dist marked E1/16S24 BT.

Each BT has a sign 54-3 and sign 54-9 attached below a 6" band of red paint, and each new BT has a brass washer marked PLS 1639 nailed flush with BT blaze.

Compass declination 19° East.

I hereby certify that the above described corner monument was properly established by me and witnessed by Jim DeMastus on June 15 1987.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*William L. Hanley*

OREGON  
JULY 14, 1978  
WILLIAM L. HANLEY  
1639

Office of..... County Surveyor..... County of Baker.....  
State of..... Oregon..... I hereby certify that the within instrument was filed in this office  
for record on the..... day of....., 19.....

(COUNTY OFFICIAL)

(DEPUTY)

FILED 12-3-87  
BAKER COUNTY SURVEYOR  
SURVEY NO. 8-45-128