

RECORD OF LAND CORNER MONUMENTATION

Description of corner evidence found and history:

Corner not previously set.

DIAGRAM

R45E
S35 T7S
E1/16 —+—
S 2 T8S
PLS699
2000

Description of monument and accessories I established to perpetuate the original location of this corner:

I set a 30" long No. 5 Rebar 26" in the ground with a yellow plastic cap marked PLS 699 at the location computed by subdividing a section in accordance with the BLM "Manual of Instructions for the Survey of Public Lands" in the drain ditch on the North side of Baker County Road No. 964.

I placed a PK nail with an aluminum washer stamped PLS 699 on the NE face at the base of a power pole which bears S46° W, 48.1 feet from the corner monument.

I placed a PK nail with an aluminum washer stamped PLS 699 on the top of the SW bridge guard post which bears S68° E, 86.5 feet from the corner monument.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Leland Lee Myers

OREGON
JULY 9, 1865
LELAND LEE MYERS
699

Renewal Date 1/1/2001

BAKER COUNTY SURVEYOR

RECEIVED APRIL 6, 2000

FILED APRIL 6, 2000

SURVEY No. 8-45-144

DWG. No. _____

INDEX No. **T8S R45E A-20**