

# RECORD OF LAND CORNER MONUMENTATION

Description of corner evidence found and history:

Corner not previously set.

## DIAGRAM

T8S R45E

S 2

NE1/16

PLS699

2000

Description of monument and accessories I established to perpetuate the original location of this corner:

I set a 30" long No. 5 Rebar 28" in the ground with a yellow plastic cap marked PLS 699 at the location computed by subdividing a section in accordance with the BLM "Manual of Instructions for the Survey of Public Lands."

I placed a 60d spike with an aluminum washer stamped PLS 699 in the base of an 8" Cottonwood tree which bears S4°E, 35.5 feet from the corner monument to the spike.

I placed a 60d spike with an aluminum washer stamped PLS 699 in the base of a 12" Cottonwood tree which bears S50°W, 66.4 feet from the corner monument to the spike.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Leland Lee Myers*

OREGON  
JULY 9, 1965  
LELAND LEE MYERS  
699

Renewal Date 1/1/2001

BAKER COUNTY SURVEYOR

RECEIVED APRIL 6, 2000

FILED APRIL 6, 2000

SURVEY No. 8-45-145

DWG. No. \_\_\_\_\_

INDEX No. **T8S R45E B-20**