



PINE MERCANTILE TRACT  
Halfway, Oregon

Map: Showing a parcel of land being subdivided from the NE<sup>1</sup>/<sub>4</sub>SE<sup>1</sup>/<sub>4</sub> Section 8, T8S, R46E, WM, Baker County, Oregon, being surveyed and staked during March, 1968 by James H. Hambleton and party, using private and public records. The line between sections 8 and 9 was measured and found to be 5284.96 feet therefore by proportionate measurements I set the S<sup>1</sup>/<sub>16</sub> cor. between sections 8 and 9, T8S, R46E WM, thence said parcel of land being more particularly described from this point. Beginning at the S<sup>1</sup>/<sub>16</sub> corner between sections 8 and 9 T8S, R46E WM, thence N89°39'W, 30.00 feet to an iron pin in the County road right-of-way; thence N89°39'W, 630.00 feet to an iron pin; thence N00°06'E, 198.00 feet to an iron pin; thence S89°39'E, 630.00 feet to an iron pin in the County road right-of-way; thence S89°39'E, 30.00 feet to the section line; thence along said section line S00°06'W, 198.00 feet to the point of beginning. Said parcel contains 3.000 acres with 0.140 acres taken out for county road right-of-way leaving 2.860 acres be the same more or less.

Scale 1" = 200'

REGISTERED  
OREGON  
LAND SURVEYOR

James H. Hambleton  
3-12-68

JULY 10, 1964  
JAMES H. HAMBLETON  
645

Found Brass Caps in  
Highway for Sec. Cor. 8/9 and  
10/11 T8S, R46E

N 89° 39' W

Note: Basis of bearing is used GLO bearing between  
Sections 8 & 9 T8S R46E WM

FILED March 28, 1973  
BAKER COUNTY SURVEYOR  
SURVEY NO. B-46-10