

NARRATIVE TO ACCOMPANY MAP OF SURVEY
A PARCEL IN THE NW $\frac{1}{4}$ NE $\frac{1}{4}$ OF SECTION 17, T. 8 S., R. 46 E., W.M.,
IN HALFWAY, OREGON
FOR JOHN AND JULIE REED

The point of beginning of description for this property is 12 rods North of the Southeast corner of the NW $\frac{1}{4}$ NE $\frac{1}{4}$ of Section 17.

The partial subdivision of Section 17 was required to determine the location of the said Southeast corner. No evidence of former monumentation for this 1/16 corner was found on the ground, and the computed location from this survey, was marked with a 5/8-inch x 30-inch steel rod.

The original plats of the various additions to Halfway indicate the East line of the NW $\frac{1}{4}$ NE $\frac{1}{4}$ is 25 feet East of the West line of Gover Lane (formerly a county road, and later Main Street extension).

This assumption was erroneous and has created descriptive and survey problems, as most of the properties in this area are described as beginning at some point North of the Southeast corner of the NW $\frac{1}{4}$ NE $\frac{1}{4}$. Further, the 1/16 line and Gover Lane are not parallel. Gover Lane bears N. 0° 10' W. and the 1/16 line bears N. 0° 32' 22" W. The East line of the NW $\frac{1}{4}$ NE $\frac{1}{4}$ is 11.0 feet East of the Southwest intersection of Gover Lane and Dawson Street.

Measurements from the Gover Lane West right of way line have apparently been made and then the 25 feet addition applied to describe the various properties from the Southeast corner of the NW $\frac{1}{4}$ NE $\frac{1}{4}$. The West line of the subject property as described is approximately 14 feet West of intended line, based on the above erroneous assumption. Fence lines between this property and the adjacent property reinforce this theory of intent.

This survey conforms to the description of record, and is marked on the ground accordingly. Mention is made herein of sources of error in the original description, the apparent intent, and lines of occupation in order to clarify reasons for faulty descriptions and to serve as basis for resolving these descriptive errors, if the need arises.

James D. Harley
Dec. 22, 1980