

Alpha-Num.
Index # J-11

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of Original corner establishment:

DIAGRAM
T8S R46E
1/4 S9
S16

The original corner was set by N. O. Walden, Deputy Surveyor under contract no. 198 dated July 15, 1873 as part of a subdivisional survey of T. 8 S., R. 46 E., W.M.

The original notes state: Set sandstone 14x8x8 in. in the ground for 1/4 sec. corner.

Description of corner evidence found:

No evidence of any corner was found. Oregon State Highway 86 Drawing by Idaho Power Company, dated July 1959 shows that the subject 1/4 corner was found but failed to identify what was found or who set the corner. Due to the ferrous metallic nature of the aggregate used for the asphalt road surface it is difficult to determine if a iron pin, pipe etc. still remains below the road surface as corner evidence. The Idaho Power Co. corner position was accepted and reestablished from record distances from found controlling points as shown on said drawing. Control points used are reference pins on the South and North right of way of I.P.C. Centerline Stationing 995+50.44 and the South 1/4 corner position of Section 16 (not found) as computed from previous surveys of record.

Description of monument and accessories I established to perpetuate the original location of the corner:

At the position of the calculated corner position set a 5/8" x 18" rebar with a yellow plastic cap marked "Hanley Engr. PLS 1206" flush to the road surface.

Corner monument references: Four 1" x 2 1/2" magnets encased in plastic were set 6 in. below the ground surface. From the monument:

A silver magnet marked "1" bears N. 54° 52' E., 48.2 ft. dist.
A pink magnet marked "2" bears S. 69° 26' E., 97.1 ft. dist.
A blue magnet marked "3" bears "3" S. 55° 19' W., 47.0 ft. dist.
A orange magnet marked "4" bears N. 18° 33' W., 32.8 ft. dist.

Reference survey: See CS 8-46-53MP

I James D. Hanley certify that this corner was properly reestablished and monumented as witnessed by Larry McBroom and Eric Striker on August 14, 1997.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

James D. Hanley
OREGON
SEPTEMBER 23, 1977
JAMES D. HANLEY
1206

Renews June 30, 1999

FILED OCT. 29, 1997
BAKER COUNTY SURVEYOR
SURVEY NO. 8-46-75

10-29-97