

AFFIDAVIT OF CORRECTION

B0030 0134

STATE OF OREGON }  
COUNTY OF BAKER } SS

I, Leland Lee Myers, a Professional Land Surveyor registered in the State of Oregon, of 587 E. Auburn Street, PO Box 99, Sumpter, OR 97877, being first duly sworn, depose and say that when I prepared Partition Plat No. P2000-003, which was recorded with the Baker County Clerk on July 21, 2000, I made an error by leaving out on course in the description of the property partitioned in the Surveyor's Certificate. The correct description for the Certificate is as follows:

The Point of Beginning for this partition is a point 100 feet East of the quarter corner between Sections 16 and 21, T8S, R46E, WM, said point being on the Easterly right-of-way line of the Relocated Baker-Homestead Highway; thence, N0°04'W, 310 feet along the said right-of-way line; thence, East, 294.35 feet to a point which is 5 feet East of the East bank of the McMullen Ditch; thence, Northeasterly along a line which is 5 feet Easterly and parallel to the said East bank to intersect the Westerly right-of-way line of the Old Baker Cornucopia Stage Road (also known by OSHD as State Highway Spur 12 and as the old Baker-Halfway Highway); thence, Southeasterly along the said westerly right-of-way line approximately 1250 feet to a point opposite of and 30 feet distant from OSHD Centerline Station PT 76+83.6; thence, on a 174.63 foot radius curve right approximately 347.1 feet to a point opposite and 30 feet Northerly of OSHD Sta. PC 72+77.0 to a point of tangency on the Old Cornucopia Stage Road right-of-way; thence, Northerly 10 feet at right angle to the said Old Road, increasing right-of-way width from 30 feet to 40 feet from Old Road centerline; thence, Southwesterly along the said right-of-way line approximately 336.4 feet; thence, N89° 44'W, approximately 94 feet; thence, S25°37'E, 41 feet returning to the said right-of-way line; thence, continuing Southwesterly along the said right-of-way line approximately 235 feet to the property corner described in Baker County DV 126-477; thence, N25°40'W, 154.78 feet; thence N89°57'50"W, 236.51 feet; thence, S26°37'38"E, 256.37 feet to the said Northerly Old Cornucopia Stage Road right-of-way; thence, along the said right-of-way S64°39'36"W, 291.93 feet; thence, N0°03'33"W, 254.48 feet; thence, West, 330.00 feet to the Easterly right-of-way line of relocated Baker-Homestead Highway; thence, N0°04'W, 730.7 feet to the Point of Beginning;

The entire property is in the ownership of Ellingson Lumber Company, the partitioner. No other errors or corrections are known to be necessary at this time.


IN WITNESS WHEREOF, I hereunto set my hand this 24<sup>th</sup> day of July, 2000.

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

OREGON  
JULY 9, 1965  
LELAND LEE MYERS  
699

Renewal Date 1/1/01

Subscribed and sworn to before me this 24<sup>th</sup> day of July, 2000.



Joni L. Thompson  
Notary Public of Oregon

My Commission expires July 29, 2000

I have examined this Affidavit of Correction and find the changes shown are permitted under ORS 92.170.

Thomas J. Hawley 7-21-2000  
Baker County Surveyor

STATE OF OREGON }  
County of Baker } SS

I certify that this instrument was received and recorded in the book of records of said county.

Julia Woods  
Baker County Clerk

by: Charlotte Beck Deputy.

FILED JULY 25, 2000

BAKER COUNTY SURVEYOR

SURVEY NO. 8-46-92

DOC#: 00300134B  
RCPT: 59616 21.00  
7/25/2000 8:30 AM ck  
REFUND: .00