



BASIS OF BEARING  
(N. 0° 17' 46" W., 2587.98')

SLAUGHTER HOUSE ROAD  
(N. 0° 17' 46" W., 2587.98')

SET 5/8" x 1' LONG REBAR  
W/ YELLOW PLASTIC CAP  
MARKED "HANLEY ENGR.  
PLS 1817" IN ASPHALT

DEED 99 47 063  
[450']  
[450']

**LINE TABLE**

LINE	BEARING	DISTANCE
L1	N. 89° 01' 56" E.	300.00'
L2	S. 0° 17' 46" E.	215.00'
L3	S. 89° 01' 56" W.	300.00'
L4	N. 0° 17' 46" W.	215.00'

WEST 1/4 CORNER, SECTION 4  
FD. BADLY BENT SPIKE SET  
IN ASPHALT. REPLACED SPIKE  
WITH 5/8" REBAR W/YELLOW  
PLASTIC CAP MARKED "HANLEY  
ENGR. PLS 1817".

**LEGEND**

- Set 5/8" x 30" rebar with plastic cap marked "HANLEY ENGR. PLS 1817" or as noted.
- Found, 5/8" rebar with plastic cap marked "HANLEY ENGR. PLS 1206".
- ( ) Record Data Per Ba. Co. Sur. No. 8-46-41.
- [ ] Record Data Per Ba. Co. Deed No. 99 47 060 & 99 47 063.



**REFERENCES**

- Baker County Survey No. 8-46-17.
- Baker County Survey No. 8-46-41.
- Baker County Survey No. 8-46-45.
- Baker County Deed No. 78 40 117.
- Baker County Deed No. 80 13 015.
- Baker County Deed No. 99 47 060.
- Baker County Deed No. 99 47 063.

SCALE: 1" = 200'

**NARRATIVE**

The purpose of this survey for Dave Huff is to mark on the ground with proper monumentation the South line of the North half of the North half of the Northwest quarter of Section 4, and the corners of a property line adjustment as shown hereon. Baker County Survey No. 8-46-41 provided the proper subdivision of Section 4. Monumentation from said Survey No. 8-46-41 was recovered and held as the basis of bearing as shown hereon. Baker County Deeds 78 40 117 and 80 13 015 provided the descriptions for the properties involved.

**HANLEY ENGINEERING, INC.**  
P.O. BOX 701, 2043 MAIN STREET, BAKER CITY, OREGON 97814 (541) 523-3803

**MAP OF SURVEY  
FOR PROPERTY LINE ADJUSTMENT  
NW1/4 OF SECTION 4, T. 8 S., R. 46 E., W.M.  
BAKER COUNTY, OREGON**

Surveyed July 30, 2004  
for Dave Huff  
Scale: 1" = 200'

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

*Thomas J. Hanley*  
OREGON  
JULY 13, 1979  
THOMAS J. HANLEY  
1817

FILED August 31, 2004  
BAKER COUNTY SURVEYOR  
SURVEY NO. B-46-104

Renews June 30, 2005