

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. N-21

History of original corner establishment:

Corner was originally established by William R. Gradon under G. L. O. contract No. 409 during May 26, to June 6, 1882. Surveyors General's notes state: "Set basalt stone 24 X 12 X 4 ins. 15 ins. in the ground for cor. to secs. 13, 14, 23 & 24, marked 3 notches S and 1 notch E edges from which A Pine 18 ins. in diam. bears N50°E, 30 lks. dist. marked T9SR36ES13 BT. A Fir 8 ins. diam. bears S40°E, 18 lks. dist. marked T9SR36ES24 BT. A Fir 14 ins. in diam. bears S20°W, 14 lks. dist. marked T9SR36ES23 BT. A Pine 24 ins. in diam. bears N80°W, 58 lks. dist. marked T9SR36ES14 BT. May 26, 1882."

DIAGRAM

T9S	R36E
S14	S13
S23	S24

Description of corner evidence found:

Found no trace of corner stone. Corner falls on a steep hillside that has been logged. Found 18" White Fir with grown over blazes and barely visible BT. From which measured N44°W, 12.0 ft., from which a rotten stump, no scribing, bears N55°E, 20.4 ft. and a rotten stump, no scribing, bears N77°W, 43.1 ft. No trace of SW BT.

Field book #4, page 18.

Corner is about 200 ft. North of road at drain crossing.

Description of monument and accessories established to perpetuate the original location of this corner

At the above described point set 2 1/2" X 30" galvanized pipe and brass cap marked:
Set pipe 20" in the ground to bedrock and placed mound of stone around to cap.

T9S	R36E
S14	S13
S23	S24

OR PLS 1051
1979

From which by magnetic declination of N20°E:
An 11" Fir bears N71°E, 44.6 ft. scribed T9SR36ES13 BT. A 14" Fir bears S65°E, 32.4 ft. scribed T9SR36ES24 BT. An 8" Fir bears S79°W, 7.5 ft. scribed T9SR36ES23 BT. A 12" Fir bears N19°W, 24.0 ft. scribed T9SR36ES14 BT. Placed 54-3s and brass washer stamped PLS 1051 on the BTs. Old BT has 54-3. Painted blazes red and 6" red band around. Placed 54-4 on a steel fence post 5' West of corner.

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

I hereby certify that the above corner monument was reestablished as herein described.

Witnesses: Daniel T. Rowland
Ronald Gilroy

November 21, 1979

Office of _____ County Surveyor _____ County of _____ Baker _____
State of _____ Oregon _____, I hereby certify that the within instrument was filed in this office
for record on the 27 day of June 1980
James D. Hanley by _____ Tom Hanley
(COUNTY OFFICIAL) (DEPUTY)

June 27, 1980

FILED June 27, 1980
BAKER COUNTY SURVEYOR
SURVEY NO. 9-36-9