

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

Index File No. N-25

History of original corner establishment:

Corner was originally established by E. McCormack under G. L. O. contract No. 398, during September 28, 1881. Surveyors General's notes state: "Set post 4 ft. long 4 ins. square 24 ins. in the ground for corner to Sec's. 13 - 18 - 19 & 24 marked: T9S S18 on NE, R37E S19 on SE, R36E S24 on SW and S13 on N. W. face, with 3 Notches on N. and S. edges from which, A pine 30 ins. diam. bears N65°E, 36 lks. dist. marked T9SR37ES18 BT. A pine 10 ins. diam. bears S70°E, 60 lks. dist. marked T9SR37ES19 BT. A pine 20 ins. diam. bears S35°W, 11 lks. dist. marked T9SR36ES24 BT. A pine 20 ins. diam. bears N85°W, 13 lks. dist. marked T9SR36ES13 BT."

DIAGRAM

```

      T9S
R36E R37E
S13  +  S18
S24  +  S19
    
```

Description of corner evidence found:

Found no trace of record corner post. Found a 20" pine stump with scribed BT. Measured S85°E, 8.0 ft. and S73°E, 39.4 ft. found rotten stump hole, and down and rotten 14" pine with full faint scribing. No trace of the Southwest and Northeast BTs could be found.

Field book #3, page

Corner falls in old skid road, about 100 ft. East of a drain on West slope.

Description of monument and accessories I established to perpetuate the original location of this corner:

At the center of the above described point, set 2 1/2" X 30" galvanized pipe and brass cap marked: Set pipe 25" in the ground and mound of stone around to cap.

```

      T9S
R36E R37E
S13  +  S18
S24  +  S19
OR PLS 1051
1979
    
```

By which by magnetic declination of N20°E:
A 12" Pine bears N23°E, 15.0 ft. scribed T9SR37ES18 BT. A 12" Pine bears S87°E, 28.0 ft. scribed T9SR37ES19 BT. A 15" Pine bears S08°W, 42.0 ft. scribed T9SR36ES24 BT. A 10" Tamarac bears N61°W, 53.4 ft. scribed T9SR36ES13 BT. Placed 54-3s and brass washers stamped PLS 1051 on the BTs. Placed 54-3 on the old BTs. Painted blazes red and 6" red band around. Placed 54-4 on a steel fence post 5' North of the corner.

I hereby certify that the above corner monument was reestablished as herein described.

Witnesses: Daniel T. Rowland
Ronald Gilroy

November 16, 1979

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

Barry B. Barbour

**OREGON
OCT. 17, 1975
BARRY B. BARBOUR
1051**

Office of.....County Surveyor.....County of.....Baker.....
Oregon
State of....., I hereby certify that the within instrument was filed in this office
for record on the.....27.....day of June....., 1980.
James D. Henley by *Tam Henley*
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

June 27, 1980

FILED June 27, 1980

BAKER COUNTY SURVEYOR

SURVEY NO. 9-36-10

☆ GPO—798-276