

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

Index File No. P-21

Corner was originally established by William R. Graddon under G. L. O. contract No. 409 during May 26, to June 6, 1882. Surveyors General's notes state: "Set basalt stone 18 X 10 X 8 ins. 12 ins. in the ground for 1/4 sec. cor., marked 1/4 on W. face, from which A pine 8 ins. in diam. bears N75°E, 34 lks. dist. marked 1/4S BT. A pine 12 ins. diam. bears N35°W, 13 lks. dist. marked 1/4S BT."

DIAGRAM

T9S R36E

1/4

S23 + S24

Description of corner evidence found:

Found 12" Pine scribed 1/4S BT. Measured S35°E, 8.6 ft. No trace or marked stone could be found. A small mound of stone was found about 4' West. Approximately N75°E, 22 ft., found old stump and hole. No trace of scribing.

Field book #3, page

Corner is about 200 ft. South of a logging road on NW slope.

Description of monument and accessories established to perpetuate the original location of this corner

At the center of the above described point, set 2 1/2" X 30" galvanized pipe and brass cap marked: Set pipe 24" in the ground and mound of stone around to cap.

From which by magnetic declination of N20°E:

A 20" Pine bears S57°E, 72.8 ft. scribed 1/4S24 BT. Placed 54-3 on old and new BT. Placed brass washer stamped PLS 1051 on new BT. Painted blazes red and 6" red band around. Placed 54-4 on a steel fence post 5' South of the corner.

T9S R36E

1/4

S23 + S24

OR PLS 1051

1979

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

Barry B. Barbour

**OREGON
OCT. 17, 1973
BARRY B. BARBOUR
1051**

I hereby certify that the above corner monument was reestablished as herein described.

Witnesses: Daniel T. Rowland
Ronald Gilroy

November 16, 1979

Office of County Surveyor County of Baker
State of Oregon, I hereby certify that the within instrument was filed in this office
for record on the 27 day of June 1980
James D. Hanley by Tom Hanley
(COUNTY OFFICIAL) (DEPUTY)

June 27, 1980

FILED June 27, 1980
BAKER COUNTY SURVEYOR
SURVEY NO. 9-36-11