


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

The corner was originally established by Arthur Philbrick under Mineral Survey No. 477, during June and July 1902. The original notes state that at the corner a scribed slate stone, 24" by 15" by 12", was set 12" in the ground and surrounded with a mound of earth from which:
An 18" red fir bears S80°10'W-14.1'.
A 14" red fir bears N75°09'E-16.5'.
Both marked B.T.B.MT. 4-S. 2-477.

DIAGRAM



Bald Mountain Cor 4
Saginaw Cor 2

Description of corner evidence found:

Found a 24" by 15" by 12" slate stone, broken into 3 pieces, the bottom of the stone still set in the original location. Chisel marks are evident on the stone. From the stone:

A 36" white fir bears S80½°W-15.0' with scribing visible on opened blaze (original bearing tree).
A 24" white fir bears N76½°E-17.1' with scribing visible on opened blaze (original bearing tree).

Description of monument and accessories | established to perpetuate the

original location of this corner:

Set a 2½" by 30" aluminum pipe with a 2½" aluminum cap 24" in the ground and surrounded with a mound of stone. Placed original stone monument in stone mound. alongside new monument. From the new monument:


An 8" white fir bears S69°W-25.3' scribed 4-BM-2-S-477 BT.
New bearing tree has a brass washer stamped PLS 1106 nailed to the face of blaze. Attached signs 54-9 and 54-3 to each bearing tree and painted face of blaze and a 6" red band around each bearing tree. Set steel fence posts on National Forest Boundary NW and SE of corner and attached sign 54-9 to one post and 54-2 to both posts.

Used steel tape and staff compass with 20°E declination, measured to the center of the bearing trees.

This corner was remonumented on July 24, 1985.

Witness: John Tuttle

Cap is marked:



1985 PLS 1106

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of.....County Surveyor..... County of.....Baker.....
State of.....Oregon....., I hereby certify that the within instrument was filed in this office
for record on the...27... day of.....Aug....., 19...85
..... by
(COUNTY OFFICIAL) (DEPUTY)