

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

The corner was originally established by Arthur Philbrick under Mineral Survey No. 477, during the survey of June and July 1902. The original notes state that at the corner a scribed slate stone, 24" by 18" by 8", was set 12" in the ground and surrounded with a mound of earth from which:

- A 10" black pine bears N77°47'W-17.56'.
- A 10" red fir bears S67°05'E-31.48'.
- Both marked B.T.A.1-477.

DIAGRAM

MS 477



Albine Cor. 1

Description of corner evidence found:

Found a 20" by 14" by 7" slate stone with an "X" on the top and chisel marks on the side protruding 10" from the ground from which:

- A 30" ponderosa pine stump bears N75°W-18.3' with catface (original bearing tree)

Description of monument and accessories I established to perpetuate the original location of this corner:

Set a 2½" by 30" aluminum pipe with a 2½" aluminum cap 24" in the ground and surrounded with a mound of earth and stone. Buried the stone monument in the ground beside the new monument. From the new monument:

- A 9" white fir bears N70½°W-5.9' scribed 1-A-477 BT.
- A 12" white fir bears S37½°E-17.4' scribed 1-A-477 BT.
- Two bearing trees have a brass washer stamped PLS 1106 nailed to face of blaze.
- Attached sign 54-3 and 54-9 to each bearing tree and painted face of blaze and 6" red band around each bearing tree. Set steel fence posts on National Forest Boundary SW and SE of corner and attached sign 54-9 to one post and 54-2 to both posts.

Used steel tape and staff compass with 20°E inclination, measured to the center of the bearing trees.

This corner was remonumented on August 14, 1985.

Witness: John Tuttle

REGISTERED  
PROFESSIONAL  
LAND SURVEYOR

William R. Wells

OREGON  
JULY 22, 1977  
WILLIAM R. WELLS  
1106

Cap is marked:

MS 477



1985  
PLS 1106

Office of...County Surveyor.....County of...Baker.....  
State of...Oregon....., I hereby certify that the within instrument was filed in this office  
for record on the...8...day of...Oct....., 1985  
.....by.....  
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

FILED  
BAKER COUNTY SURVEYOR  
SURVEY NO. 9-36-47