


CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

The corner was originally established by Arthur Philbrick under Mineral Survey No. 477, during the survey of June and July 1902. The original notes state that at the corner a scribed slate stone, 24" by 18" by 12", was set 12" in the ground and surrounded with a mound of earth and stone from which:

- A 20" red fir bears N87°40'-8.83'.
- A 14" red fir bears N15°18'W-29.59'.
- Both marked B.T.B.Mt.3-S.3-477.



Bald Mountain Cor. 3
Saginaw Cor. 3

Description of corner evidence found:

Found a 24" by 18" by 12" slate stone with chisel marks and an "X" on the top from which:

- A 30" white fir stump bears N16½°W-30.4' with catface (original bearing tree).
- The rotted remains of a white fir bear N88°W-9'± with fragmentary scribing visible (original bearing tree).

Description of monument and accessories established to perpetuate the original location of this corner:

Set a 2½" by 30" aluminum pipe with a 2½" aluminum cap 24" in the ground and surrounded with a mound of earth and stone. Buried stone monument in the mound beside the new monument. From the new monument:

- A 7" engleman spruce bears N66½°W-17.4' scribed 3-BM-3-S-477 BT.
- A 6" white fir bears N65½°E-5.1' scribed 3-BM-3-S-477 BT.
- The new bearing trees have a brass washer stamped PLS 1106 nailed to face of blaze. Attached signs 54-3 and 54-9 to each bearing tree and painted face of blaze and a 6" red band around each bearing tree. Set steel fence posts on National Forest Boundary NW and SE of corner and attached sign 54-9 to one post and sign 54-2 to both posts.

Used steel tape and staff compass with 20°E inclination, measured to the center of the bearing trees.

This corner was remonumented on August 14, 1985.


Witness: John Tuttle

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Cap is marked:
MS 477



Office of.....County Surveyor.....County of.....Baker.....
State of.....Oregon....., I hereby certify that the within instrument was filed in this office
for record on the...8... day of.....Oct....., 1985
..... by
(COUNTY OFFICIAL) (DEPUTY)