

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

History of original corner establishment:

The corner was originally established by Arthur Philbrick under Mineral Survey No. 477, during the survey of June and July 1902. The original notes state that at the corner a stone, 24" by 18" by 15", was set 12" in the ground surrounded with a mound of stone from which:

A 20" tamarack bears S22°05'W-162.67' scribed B.T.S.1-477. Saginaw Cor 1

DIAGRAM

MS 477

S
Cor 1

Description of corner evidence found:

Found a 12" by 12" by 24" stone in a mound of stone. Chisel marks were not visible. From the stone:

A 22" down western larch bears S22°W-163'± with faint scribing on open blaze (original bearing tree).

Description of monument and accessories established to perpetuate the original location of this corner:

Set a 2½" by 30" aluminum pipe with a 2½" aluminum cap 20" in the ground and surrounded with a mound of earth and stone. Buried the original stone in the mound next to the new monument. From the new monument:

A 10" ponderosa pine bears N51°W-17.4' scribed 1-S-477 BT.

A 9" white fir bears N11½°E-33.9' scribed 1-S-477 BT.

New bearing trees have a brass washer stamped PLS 1106 nailed to face of blaze. Attached signs 54-3 and 54-9 to each bearing tree and painted face of blaze and a 6" red band around each bearing tree. Set steel fence posts on National Forest Boundary NW and NE of corner and attached sign 54-9 to one post and sign 54-2 to both posts.

Used steel tape and staff compass with 20°E declination, measured to the center of the bearing trees.

This corner was remonumented on August 14, 1985.

Witness: John Tuttle

Cap is marked:

MS 477

S
Cor 1

1985
PLS 1106

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of.....County Surveyor.....County of.....Baker.....
State of.....Oregon....., I hereby certify that the within instrument was filed in this office
for record on the...8... day of.....Oct....., 1985
..... by
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

☆ GPO—798-276

FILED

BAKER COUNTY SURVEYOR

SURVEY NO. 9-36-54