

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

N-17

History of original corner establishment:

This corner was originally established by William R. Graddon, U.S. Deputy Surveyor, under his Contract No. 409, dated March 28, 1882, during May and June, 1882. The original notes state that at the corner a 15" by 9" by 7" marked granite stone was set 10" in the ground from which:

- A 20" pine bears N5°E-21 lks, marked T9S R36E S14 BT.
- A 20" fir bears S5°E-23 lks, marked T9S R36E S23 BT.
- A 10" fir bears S70°W-27 lks, marked T9S R36E S22 BT.
- A 10" fir bears N75°W-22 lks, Marked T9S R36E S15 BT.

DIAGRAM

T9S R36E	
S15	S14
S22	S23

Description of corner evidence found:

Scattered mound of stone with one 15" by 9" by 5" granite stone with no discernable marks from which:

- A 30" western larch bears N5°E-13.9' with healed blaze (original bearing tree).
- A down, rotten white fir bears S5°E-26' with scribing visible on a partly healed blaze (original bearing tree). Measured to apparent root hole.
- A down 21" white fir bears S70°W-17.8' to root hole with healed blaze (original bearing tree).
- A down 18" douglas fir is lying across the down SW bearing tree, the douglas fir is the NW bearing tree but its root hole location could not be determined.

Description of monument and accessories established to perpetuate the original location of this corner:

Set a 2½" by 30" aluminum pipe with 2½" aluminum cap 15" in the ground and surrounded with a mound of earth and stone. Buried corner stone alongside new monument in the mound. From the corner:

- A 6" white fir bears N47½°W-20.3' scribed T9S R36E S15 BT.
- A 19" white fir bears S26½°E-49.0' scribed T9S R36E S23 BT.
- A 12" white fir bears S21°W-31.3' scribed T9S R36E S22 BT.

New bearing trees have a brass washer stamped PLS 1106 nailed to the face of blaze. Attached sign 54-3 and 54-9 and painted face of blaze and a 6" red band around each bearing tree. Set steel fence post north of corner and attached sign 54-9.

Used steel tape and staff compass with 20°E declination, measured to the center of the bearing trees.

This corner was remonumented on September 24, 1985.

Witness: Willard Hulick

Cap is marked:

T9S R36E	
S15	S14
S22	S23
1985	
PLS 1106	

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of _____ County Surveyor _____ County of _____ Baker
State of _____ Oregon _____, I hereby certify that the within instrument was filed in this office
for record on the _____ day of _____, 19____
_____ by _____
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

FILED 12-31-85
BAKER COUNTY SURVEYOR
SURVEY NO. 9-36-78

☆ GPO—798-276