

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

E-21

History of original corner establishment:

This corner was originally established by William R. Cradon, U.S. Deputy Surveyor, under his Contract No. 409, dated March 28, 1882, during May and June, 1882. The original notes state that at the corner a 18" by 12" by 5" marked basalt stone was set 12" in the ground from which:

A 30" pine bears S80°E-25 lks, scribed T9S R36E S12 BT.
A 30" pine bears N 55°E-8 lks, scribed T9S R36E S1 BT.
A 28" pine bears S 75°W-25 lks, scribed T9S R36E S11 BT.
A 14" pine bears N70°W-39 lks, scribed T9S R36E S2 BT.

DIAGRAM

T9S R36E
S2 | S1
S11 | S12

Description of corner evidence found:

The corner monument was either destroyed by logging or slid down the steep hill. The corner position was reestablished from the location of three bearing tree stumps found in original position-measuring record bearing and distance from each of the three stumps and placing the reestablished corner in the center of the triangle formed by the measurements. The original location of the SE bearing tree could not be determined accurately. From the reestablished corner:

A 30" pon. pine stump bears N60°E-6.0' with scribing visible on open blaze.
A 36" pon. pine stump bears S 73°W-17.3' with healed blaze.
A 17" pon. pine stump bears N69°W-26.1' with healed blaze.
A 24" uprooted pon. pine bears S80°E-16.5' with burnt out blaze.

Description of monument and accessories established to perpetuate the original location of this corner:

Set a 2 1/2" by 30" aluminum pipe with 2 1/2" aluminum cap 24" in the ground and surrounded with a mound of earth and stone from which:

A 6" white fir bears N23 1/2°E-23.7' scribed T9S R36E S1 BT.
A 8" pon. pine bears S70°E-26.6' scribed T9S R36E S12 BT.
A 13" white fir bears S 67 1/2°W-43.6' scribed T9S R36E S11 BT.
A 9" douglas fir bears N2 1/2°W-49.5' scribed T9S R36E S2 BT.

New bearing trees have a brass washer stamped PLS 1106 nailed to the face of blaze. Attached sign 54-3 and 54-9 and painted face of blaze and a 6" red band around each bearing tree. Set Steel fence post North of corner and attached sign 54-9.

Used steel tape and staff compass with 20°E declination, measured to the center of the bearing trees.

This corner was remonumented on September 24, 1985.

Witness: Willard Hulick.

Cap is marked:

T9S R36E
S2 | S1
S11 | S12
1985
PLS 1106

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of.....County Surveyor.....County of.....
Oregon
State of....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19....

(COUNTY OFFICIAL)

(DEPUTY)