

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

J-21

History of original corner establishment:

This corner was originally established by William R. Graddon, U.S. Deputy Surveyor, under his Contract No. 409, dated March 28, 1882, during May and June, 1882. The original notes state that at the corner a 18"by12" by 4" marked basalt stone was set 12" in the ground from which:

DIAGRAM

T9S R36E	
S11	S12
S14	S13

- A 20" tamarack bears N65°E-67 lks, scribed T9S R36E S12 BT.
- A 36" pine bears S35°E-52lks, scribed T9S R36E S13 BT.
- A 30" pine bears S65°W-78 lks, scribed T9S R36E S14 BT.
- A 18" tamarack bears N65°W-70 lks, scribed T9S R36E S11 BT.

Description of corner evidence found:

A 15"by12"by4" basalt stone lying loose on the ground. The corner position was reestablished at the center of the square formed by measuring record bearing and distance from each of the bearing trees. From the reestablished corner position:

- A 14" western larch snag bears N66½°W-46.9' with scribing visible on a partly healed blaze.
- A 24" pon. pine stump bears S66°W-52.1' with a portion of the blaze visible.
- A 30" pon. pine stump bears S35°E-34.9' with scribing visible.
- A 17" western larch stump bears N64½°E-44.7' with scribing visible on a partly healed blaze.

Description of monument and accessories established to perpetuate the original location of this corner:

Set a 2½" by 30" aluminum pipe with 2½" aluminum cap 24" in the ground and surrounded with a mound of earth and stone. Buried corner stone in the new mound. From the new monument:

- A 9" white fir bears N55½°E-16.2' scribed T9S R36E S12 BT.
- A 9" western larch bears S52°E-35.5' scribed T9S R36E S13 BT.
- A 7" pon. pine bears S 7½°W-21.0' scribed T9S R36E S14 BT.
- A 7" lodgepole pine bears N 68½°W-15.1' scribed T9S R36E S11 BT.

New bearing trees have a brass washer stamped PLS 1106 nailed to the face of blaze. Attached sign 54-3 and 54-9 and painted face of blaze and a 6" red band around each bearing tree. Set steel fence post North of corner and attached sign 54-9.

Used steel tape and staff compass with 20°E declination, measured to the center of the bearing trees.

Cap is marked:

T9S R36E	
S11	S12
S14	S13

1985
PLS 1106

This corner was remonumented on October 8, 1985.

Witness: Willard Hulick.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of.....County.....Surveyor..... County of Baker
State of Oregon....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL)

(DEPUTY)

Form R6-7100-57 (9/71)

FILED 12-31-85
BAKER COUNTY SURVEYOR
SURVEY NO. 9-36-80

☆ GPO—798-276