

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

A-11

History of original corner establishment:

This corner was originally established by Eugene P. McCornack, U.S. Deputy Surveyor, under his Contract No. 398, dated July 2, 1881, during his surveys beginning August 15, 1881. The original notes state that at the corner a marked 3" square by 3' long post was set 24" in the ground for the corner to sections 4 and 33 from which:
A 24" fir bears N45°W-14 lks, marked 1/4 S BT.
A 12" fir bears S75°W-13 lks, marked 1/4 S BT.

DIAGRAM

1/4 S4
T9S R36E

In 1937, Otis Gould, U.S. Cadastral Surveyor, under special instructions dated Nov. 27, 1935, during his surveys in July through October, 1937, recovered the corner and changed it to refer to section 4 only. Gould's notes state that at the corner point a marked brass cap on a 1" by 3' long iron post was set 27" in the ground from which:

A 24" fir stump bears N45°W-14 lks, marked 1/4 S BT(Old BT- Obliterate marks).
A dead fir, 18" in dia. bears S85°E-13 lks, marked 1/4 S BT (Old BT).

Description of corner evidence found:

A 10" fir bears S85°E-18 lks, marked 1/4 S4 BT. (New BT).
A 12" fir bears S63°W-37 lks, marked 1/4 S4 BT. (New BT).

Found a 2 1/2" brass cap on a 1" iron pipe protruding 9" from a mound of earth and stone from which:

A 20" green topped white fir bears S81°E-9.2' with scribing vis. on open blaze.
A 14" white fir bears S85°E-11.4' with healed blaze.
A 16" white fir bears S54 1/2°W-23.5' with healed blaze.

Description of monument and accessories I established to perpetuate the original location of this corner:

Built a mound of stone to the top of the monument. Attached sign 54-3 and 54-9 and painted face of blaze and a 6" red band around each bearing tree. Set steel fence post East of corner and attached sign 54-9.

Used steel tape and staff compass with 20°E declination, measured to the center of the bearing trees.

The cap is a standard GLO brass cap marked:

This corner was maintained on September 18, 1985.

Witness: Bob English.

1/4 S4

1937

REGISTERED
PROFESSIONAL
LAND SURVEYOR

Willie R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of...County Surveyor..... County of...Baker.....
State of...Oregon....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

☆U.S. GOVERNMENT PRINTING OFFICE - 1983-793-276

FILED 2-12-1986
BAKER COUNTY SURVEYOR
SURVEY NO. 9-36-82