

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

A-13

History of original corner establishment:

This corner was originally established by Eugene P. McCornack, U.S. Deputy Surveyor, under his Contract No. 398, dated July 2, 1881, during his surveys beginning August 15, 1881. The original notes state that at the corner a 4' long by 4" square marked post was set 24" in the ground for the corner to Sections 3, 4, 33, and 34 from which:

- A 14" black pine bears N70°E-18 lks, marked T8S R36E S34 BT.
- A 14" black pine bears S45°E-36 lks, marked T9S R36E S3 BT.
- A 12" black pine bears S45°W-17 lks, marked T9S R36E S4 BT.
- A 14" black pine bears N80°W-25 lks, marked T8S R36E S33 BT.

DIAGRAM

T8S R36E
S34
S4 | S3
T9S R36E

In 1937, Otis Gould, U.S. Cadastral Surveyor, under special instructions dated Nov. 27, 1935, during his surveys in July through October, 1937, recovered the corner and changed it to refer to Sections 3 and 4 only. Gould's notes state that at the corner point a marked brass cap on a 2" by 3' long iron post was set 27" in the ground with the orig. post buried at the base of the monument from

Description of corner evidence found:

which:

- A 16" dead and fallen pine bears N70°E-18 lks, marked T8S R36E S34 BT (Old BT-Obliterated marks).
- A 16" dead pine bears S36°E-36 lks, marked T9S R36E S3 BT (Old BT).
- A 16" dead and fallen pine bears S45°W-17 lks, marked T9S R36E S4 BT (Old BT).
- A 16" dead pine bears N80°W-25 lks, marked T8S R36E S33 BT. (Old BT Obliterate marks).
- A 20" tamarack bears S63½°E-68 lks, marked T9S R36E S3 BT (New BT).
- A 12" tamarack bears S40°W-14 lks, marked T9S R36E S4 BT (New BT).

Found a 2½" brass cap on a 2" iron pipe protruding 10" from an earth mound from which:

- A 14" lod. pine stump and tree bears S36°E-23.8' with vis. scribing on open blaze.
- A 10" down lod. pole pine bears S45°W-11.2' with scribing vis. on open blaze.
- A 17" w. larch stump bears S61½°E-44.4' with scribing vis. on partly healed blaze.
- A 15" w. larch stump bears S43½°W-9.7' with healed blaze.

Description of monument and accessories established to perpetuate the

original location of this corner:

Built a mound of stone around monument to the top. From the monument:

- A 9" alpine fir bears S29°E-87.8' scribed T9S R36E S3 BT.
- A 10" white fir bears S52½°W-29.2' scribed T9S R36E S4 BT.

New bearing trees have a brass washer stamped PLS 1106 nailed to the face of blaze. Attached sign 54-3 and 54-9 and painted face of blaze and a 6" red band around each bearing tree. Set steel fence post East of corner and attached sign 54-9.

Used steel tape and staff compass with 20°E declination, measured to the center of the bearing trees.

The cap is a standard GLO brass cap marked:

T8S R36E

S34
S4 | S3
T9S R36E
1937

This corner was maintained on September 18, 1985.

Witness: Bob English.

REGISTERED
PROFESSIONAL
LAND SURVEYOR

William R. Wells

OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106

Office of.....County Surveyor.....County of.....Baker.....
State of.....Oregon....., I hereby certify that the within instrument was filed in this office
for record on the.....day of....., 19.....

(COUNTY OFFICIAL)

(DEPUTY)

2-12-1986

COUNTY SURVEYOR

FILE NO. 9-36-83