

CERTIFIED RECORD OF LAND CORNER MONUMENTATION

A-15

History of original corner establishment:

This corner was originally established by Eugene P. McCornack, U.S. Deputy Surveyor, under his Contract No. 398, dated July 2, 1881, during his surveys beginning on August 15, 1881. The original notes state that at the corner a 3' long by 3" square marked post was set 24" in the ground for the corner to Sections 3 and 34 from which:

A 10" ~~black~~ pine bears N15°E-11 lks, marked 1/4 S BT.

A 10" black pine bears S40°E-7 lks, marked 1/4 S BT.

In 1937, Otis Gould, U.S. Cadastral Surveyor, under special instructions dated Nov. 27, 1935, during his surveys in July through October, 1937, recovered this corner and changed it to refer to Section 3 only. Gould's notes state that at the corner point a marked brass cap on a 1" by 3' long iron post was set 27" in the ground with the orig. wood post corner buried at the base of post from which:

A 20" pine bears N4°E-11 lks, marked 1/4 S BT. (Old BT-Obliterated marks).

Description of corner evidence found:

A 14" pine bears S46°E-7 lks, with healed blaze. (Old BT).

A 18" pine bears S53°W-74 lks, marked 1/4 S3 BT. (New BT).

Found a 2 1/2" brass cap on a 1" iron pipe protruding 5" from the earth mound from which:

A 11 1/2" standing, dead, lodgepole pine bears S34°E-4.9' with healed blaze.

A 16" down lodgepole pine bears S58°W-48.8'± with scribing vis. on open blaze.

Description of monument and accessories | established to perpetuate the original location of this corner:

Built a mound of stone to the top of monument. From the monument:

A 16 1/2" white fir bears S4°E-15.4' scribed 1/4 S3 BT.

A 7" white fir bears S45°W-12.0' scribed 1/4 S3 BT.

New bearing trees have a brass washer stamped PLS 1106 nailed to the face of blaze. Attached sign 54-3 and 54-9 and painted face of blaze and a 6" red band around each bearing tree. Set steel fence post East of corner and attached sign 54-9.

Used steel tape and staff compass with 20°E declination, measured to the center of the bearing trees.

The cap is a standard GLO brass cap marked:

— . —
1/4 S3

This corner was maintained on September 20, 1985.

Witness: Bob English.

**REGISTERED
PROFESSIONAL
LAND SURVEYOR**

William R. Wells

**OREGON
JULY 22, 1977
WILLIAM R. WELLS
1106**

Office of.....County Surveyor.....County of.....Baker
State of.....Oregon....., I hereby certify that the within instrument was filed in this office
for record on the..... day of....., 19.....

..... by
(COUNTY OFFICIAL) (DEPUTY)

Form R6-7100-57 (9/71)

☆U.S. GOVERNMENT PRINTING OFFICE - 1983-793-276

FILED 2-12-1986

BAKER COUNTY SURVEYOR

SURVEY NO. 9-36-84